



Berlin Future Land Use Plan (1992)

The map below identifies the approximate locations of three future land use categories. (Critical, Sensitive and Rural Residential)

- Critical Resource Areas (red slash) – Wetlands and slopes over 25% are unsuitable for development.
- Sensitive Natural Areas (blue slash) – Aquifers, slopes 15-25% and flood hazard areas have limitations that must be recognized if they are to be developed without health and safety problems.
- Rural Residential (unshaded) - Every lot developed for residential purposes must be able to support itself with an on-site sewage disposal system and well.



Adopted November 1, 1999, the Berlin Zoning Ordinance established a number of natural resource overlay zones intended to protect those areas with characteristics that require protection and land management practices that minimize environmental degradation. The map provided shows the approximate boundaries of each overlay zone.



Wellhead Protection Overlay Zone (blue dots) - The limits of the Wellhead Protection Overlay zone include all areas in the "Wellhead Protection Study, Berlin, NH March 1993", prepared by Provan and Lorber, Inc. The intent of this overlay zone is to:

- A. Promote the health, safety and general welfare of the community;
- B. Protect, preserve and maintain the groundwater supply and wellhead protection areas within the known aquifers of the City;
- C. Preserve and protect sources of drinking water for the public health and safety;
- D. Conserve the natural resources of the City;
- E. Protect the groundwater and wellhead protection areas of the City from adverse development or inappropriate land use practices; and
- F. Prevent blight and pollution of the environment.

Use	Restriction
General service & repair shop	SUP
Metalworking shop	SUP
Manufacturing facility	SUP
Waste & scrap processing & storage	SUP
Domestic septic system	SUP
Laboratory	SUP
Agricultural use	SUP
Stormwater infiltration pond & leaching basin	SUP
Cleaning service	SUP
Food processing plant	SUP
Wood preserving & furniture stripping	SUP
Excavation/grading	SUP
Manure/fertilizer storage	SUP
Electronic circuit assembly	SUP
Print shops & facilities	SUP
Under & above ground petroleum or chemical storage	SUP
Vehicle service & repair shops & facilities	SUP
Concrete, asphalt, and tar manufacturing	N
Fueling and maintenance of earthmoving equipment	N
Sewage/wastewater treatment system excluding domestic systems	N
Hazardous waste facility	N
Salt/deicing material storage	N
Solid waste landfill	N
Snow dump	N
Junkyard	N

N = Prohibited Use

SUP = Requires a Special Use Permit

Within the Wellhead Protection Overlay zone the following design and operations requirements shall be observed, except for single-family dwellings where these standards shall serve as guidelines only:

a. Storage

Provision shall be made to protect against toxic or hazardous material discharge or loss through corrosion, accidental damage, spillage, or vandalism through such measures as provision for spill control in the vicinity of chemical or fuel delivery points, secure storage areas for toxic or hazardous material, and indoor storage provisions for corrodible or dissolvable materials.

b. Location

Where the premises are partially outside of the Wellhead Protection Overlay zone, such potential pollution sources as on-site waste disposal systems shall, to the degree feasible (based upon engineering criteria, not financial criteria), be located outside the zone.

c. Disposal

Provisions shall be made to assure that any waste disposed into the sewers shall conform to the City of Berlin's Sewer Use Regulations. Connecting sewers from the building shall be vitreous clay pipe or any other pipe shown to provide equivalent protection against corrosion.

d. Excavation and Grading

No excavation and grading in the Wellhead Protection Overlay zone shall go below a depth of four feet (4') of clean material above the high water table.

e. Impervious Surfaces

Within the Wellhead Protection Overlay zone, no more than twenty percent (20%) of the lot shall be covered with impervious surfaces unless a stormwater management plan is prepared which ensures that stormwater recharged to groundwater will not result in violation of Ambient Groundwater Quality Standards NH Code of Administrative Rules Part Env-Ws 1403.5 at the property boundary.

f. Monitoring

Periodic monitoring may be required by the SUPGA, including sampling of wastewater disposed to off-site systems or drywells and sampling from groundwater monitoring wells to be located and constructed as specified in the Special use permit, with reports to be submitted to the SUPGA and the Board of Health, and with costs to be borne by the owner of the premises.

Wetlands Overlay Zone (blue slash) - The limits of the Wetlands Overlay zone include all wetlands and buffer area, defined as follows:

- A. Poorly drained, or very poorly drained soils as defined by the most recent USDA Natural Resource Conservation Service's soil survey;
- B. Wetlands buffer area is defined as twenty-five feet (25') from any wetland edge.

Prohibited uses include:

- A. The erection or construction of any structure.
- B. Alteration of the natural surface configuration by the addition of fill or by excavation or dredging.
- C. Uses which utilize, store, process or dispose of toxic substances that may pose a threat to surface or groundwater quality.
- D. Underground fuel storage tanks.

Steep Slope Overlay Zone (red slash) – The limits of the Steep Slope Overlay zone include all areas of natural terrain having slopes in excess of fifteen percent (15%) located within the City of Berlin.

All uses not expressly permitted outright or by special use permit shall be deemed prohibited in the Steep Slope Overlay zone.

Permitted Uses:

- A. Wildlife refuge, conservation area and nature trail.
- B. Open space, parks and outdoor recreation not requiring extensive excavation.
- C. Forestry and tree farming using best management practices to prevent soil erosion.

Uses Requiring a Special Use Permit from the Planning Board:


- A. Agriculture using best management practices to prevent erosion.
- B. Roads and driveways may be granted special use permits to cross the Steep Slopes Overlay zone subject to the following findings by the Planning Board:
 - i. the lot cannot be reasonably used without such a crossing;
 - ii. the design and construction of the crossing will not cause soil erosion, stream sedimentation, excessive loss of vegetative cover, or public maintenance costs; and
 - iii. the crossing will not adversely scar a ridge line or hillside that is a prominent visual amenity in the City.
- C. The placement, on any premises, of more than one hundred (100) cubic yards of sod, loam, sand, gravel, quarried stone or other materials being used for fill. A special use permit for fill placement in the Steep Slope Overlay zone may be granted by the Planning Board subject to the following:


- i. A plan of the land involved shall be submitted to the Planning Board showing all human-made features, property lines, vegetative cover, existing topography at four foot (4') contour intervals including land within one hundred feet (100') of the property where the proposed placement of materials is to take place. The Planning Board may require that the plan be prepared by a licensed engineer.
- ii. A plan of the land involved shall show temporary and permanent drainage and the proposed topography at two foot (2') contour intervals.
- iii. The estimated quantity of fill to be placed shall be shown on the plan and calculated using the average end-area method or by a method approved by the Planning Board.
- iv. The type of material to be used as fill shall be specified on the plan and shall not contain garbage, ashes, organic material or material detrimental to the stability of the structure of the finished grade as determined by the Planning Board.

Special Flood Hazard Area Overlay Zone (red dots) – Applies to all lands designated as special flood hazard areas by the Federal Emergency Management Agency (FEMA) in its "Flood Insurance Study for the City of Berlin, NH", together with the associated Flood Insurance Rate Maps, and Flood Boundary and Floodway Maps of the City dated June 1982.

The purpose of the Special Flood Hazard Area Overlay zone is to limit the nature and intensity of development of flood prone areas to those uses which can be appropriately and safely located in the flood plain and thereby serve the following objectives:

- A. Secure safety from floods;
- B. Prevent loss of life and reduce property damage and other losses and risks associated with flood conditions;
- C. Preserve the location, character and extent of natural drainage courses, and
- D. Maintain ecological balance.





<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OF CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - NAD 83 AND METERS NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL BY: COLIN & COLANINNO INC. & CARTOGRAPHIC ASSOCIATES INC.</p> <p>PHOTOGRAPHY BY: CHAS. H. SELLS, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT) MAY 9, 1992 (1"=2200' FLIGHT)</p> <p>COMPLETION DATE: APRIL 15, 1993</p>		<p>PRODUCED IN 1993 BY</p> <p>CARTOGRAPHIC ASSOC. INC.</p> <p>PROFESSIONAL CONSULTANTS</p> <p>MUNICIPAL MAPPING - GIS - LAND SURVEYING</p> <p>12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561</p> <p>(603)444-8768 - (800)322-4540 - FAX (603)444-1368</p>		<p>LEGEND</p> <p>M.L. = MILE</p> <p>AREA SURVEYED AC</p> <p>AREA CALCULATED AC</p> <p>RIGHT OF WAY M.L.</p> <p>RECORD DIMENSION 100'</p> <p>SCALED DIMENSION 100'</p> <p>COMMON OWNERSHIP OR</p> <p>WATER LINE M.L.</p> <p>RIGHT OF WAY M.L.</p> <p>SURFACE WATER M.L.</p> <p>WETLANDS M.L.</p>		<p>TAX EXEMPT PROPERTY B</p> <p>SUBDIVISION LOT NO. B</p> <p>BUILDING B</p> <p>LOT/RANGE B</p> <p>BLOCK NUMBER B25</p>		<p>FEET SCALE 1" = 100'</p> <p>0 50 100 150 200</p> <p>METERS</p> <p>0 25 50 75</p> <p>REVISED TO: April 1, 1993</p>		<p>PROPERTY MAP</p> <p>BERLIN</p> <p>NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN</p> <p>CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ</p>		<p>INDEX DIAGRAM</p> <p>120 128 134</p> <p>119 133</p> <p>118 130 132</p>		<p>MAP NO.</p> <p>129</p>	
---	--	--	--	---	--	--	--	--	--	---	--	---	--	----------------------------------	--





THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - MAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.
GPS CONTROL BY: COLE & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES, INC.
PHOTOGRAMMETRY BY: CHAS. H. SELLS, INC.
PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT); MAY 8, 1992 (1"=2000' FLIGHT)
COMPLETION DATE: APRIL 15, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
PROFESSIONAL CONSULTANTS
MUNICIPAL MAPPING - GIS - LAND SURVEYING
12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03561
(603)444-6788 - (800)322-454C - FAX (603)444-1368

AREA SURVEYED AC
AREA CALCULATED AC
RECORD DIMENSION 100'
SCALED DIMENSION 100'S
COMMON OWNERSHIP OR

LEGEND
M.L. MATCH LINE
R/W RIGHT OF WAY
S.W. SURFACE WATER
W.L. WETLANDS


TAX EXEMPT PROPERTY
SUBDIVISION LOT NO.
BUILDING
LOT/RANGE
BLOCK NUMBER B25

FEET SCALE 1" = 100'
0 50 100 200 300
METERS
REVISED TO : April 1 1999

PROPERTY MAP
BERLIN
NEW HAMPSHIRE
CONTRACTING AUTHORITY: CITY OF BERLIN
CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ

INDEX DIAGRAM
128/134
129/412
130/132
A

MAP NO.
133



THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.

HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - NAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.

GPS CONTROL BY COLER & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES, INC.

PHOTOGRAPHY BY CHAS. H. SELLS, INC.

PHOTOGRAPHY DATE: APRIL 28, 1992 (1"-750' FLIGHT); MAY 8, 1992 (1"-2000' FLIGHT)

COMPLETION DATE: APRIL 15, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
PROFESSIONAL CONSULTANTS
MUNICIPAL MAPPING - GIS - LAND SURVEYING
12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561
(603)444-8768 - (800)322-4540 - FAX (603)444-1366

AREA SURVEYED..... AC
AREA CALCULATED..... AC
RECORD DIMENSION..... 100'
SCALED DIMENSION..... 100'
COMMON OWNERSHIP..... ON

LEGEND
M.L. MATCH LINE
R/W RIGHT OF WAY
S.W. SURFACE WATER
W. WETLANDS

TAX EXEMPT PROPERTY.....
SUBDIVISION LOT NO.....
BUILDING.....
LOT/RANGE.....
BLOCK NUMBER..... **B25**

FEET SCALE 1" = 100'
0 50 100 200 300
METERS
REVISED TO: **April 1, 1999**

PROPERTY MAP
BERLIN
NEW HAMPSHIRE

CONTRACTING AUTHORITY
CITY OF BERLIN

CONTRACTING OFFICIAL
CITY MANAGER - MITCHELL BERKOWITZ

INDEX DIAGRAM
ON 1/4
127/135 412
128/133
129/133

MAP NO.
134



THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - NAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.
GPS CONTROL BY: COLIN & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC.
PHOTOGRAPHY BY: CHAS. H. SELLS, INC.
COMPLETION DATE: APRIL 15, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
PROFESSIONAL CONSULTANTS
MUNICIPAL MAPPING - GIS - LAND SURVEYING
12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03561
(603)444-8768 - (800)322-4540 - FAX (603)444-1368

AREA SURVEYED Ac
AREA CALCULATED AcC
RECORD DIMENSION 100'
SCALED DIMENSION 100'S
COMMON OWNERSHIP OR

LEGEND
M.L. = MILE
R/W = RIGHT OF WAY
S.W. = SURFACE WATER
W. = WETLANDS


TAX EXEMPT PROPERTY
SUBDIVISION LOT NO.
BUILDING
LOT/FRANCE
BLOCK NUMBER B25

FEET SCALE 1" = 100'
METERS
REVISED TO: April 1, 1999

PROPERTY MAP
BERLIN
NEW HAMPSHIRE
CONTRACTING AUTHORITY
CITY OF BERLIN
CITY MANAGER - MITCHELL MERRITT

INDEX DIAGRAM
126/136 405
127/137 412
128/138 413

MAP NO.
135



THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - NAD 83 AND MEETS NATIONAL MAP ACCURACY STANDARDS.
GPS CONTROL BY COLER & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC.
PHOTOGRAMMETRY BY CHAS. H. ZELLS, INC.
PHOTOGRAPHY DATE: APRIL 26, 1992 (1"=750' FLIGHT); MAY 8, 1992 (1"=2000' FLIGHT)
COMPLETION DATE: APRIL 18, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
PROFESSIONAL CONSULTANTS
MUNICIPAL MAPPING - GIS - LAND SURVEYING
12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561
(603)444-6788 - (603)222-4540 - FAX (603)444-1386

AREA SURVEYED Ac
AREA CALCULATED Ac
RECORD DIMENSION 100'
SCALED DIMENSION 100'
COMMON OWNERSHIP OR


LEGEND
MATCH LINE M.L.
RIGHT OF WAY R/W
SURFACE WATER W
WETLANDS W

TAX EXEMPT PROPERTY Ⓢ
SUBDIVISION LOT NO. Ⓛ
BUILDING B
LOT/RANGE R
BLOCK NUMBER B25

FEET SCALE 1" = 100'
0 100 200 300
METERS
April 1, 1997
REVISED TO

PROPERTY MAP
BERLIN
NEW HAMPSHIRE
CONTRACTING AUTHORITY: CITY OF BERLIN
CONTRACTING OFFICIAL: CITY MANAGER - WITHELL BOWEN

INDEX DIAGRAM
140-3
140-2
140-14
140-51
124-2
124-138
124-139
124-140
124-141
124-142
124-143
124-144
124-145
124-146
124-147
124-148
124-149
124-150
124-151
124-152
124-153
124-154
124-155
124-156
124-157
124-158
124-159
124-160
124-161
124-162
124-163
124-164
124-165
124-166
124-167
124-168
124-169
124-170
124-171
124-172
124-173
124-174
124-175
124-176
124-177
124-178
124-179
124-180
124-181
124-182
124-183
124-184
124-185
124-186
124-187
124-188
124-189
124-190
124-191
124-192
124-193
124-194
124-195
124-196
124-197
124-198
124-199
124-200
124-201
124-202
124-203
124-204
124-205
124-206
124-207
124-208
124-209
124-210
124-211
124-212
124-213
124-214
124-215
124-216
124-217
124-218
124-219
124-220
124-221
124-222
124-223
124-224
124-225
124-226
124-227
124-228
124-229
124-230
124-231
124-232
124-233
124-234
124-235
124-236
124-237
124-238
124-239
124-240
124-241
124-242
124-243
124-244
124-245
124-246
124-247
124-248
124-249
124-250
124-251
124-252
124-253
124-254
124-255
124-256
124-257
124-258
124-259
124-260
124-261
124-262
124-263
124-264
124-265
124-266
124-267
124-268
124-269
124-270
124-271
124-272
124-273
124-274
124-275
124-276
124-277
124-278
124-279
124-280
124-281
124-282
124-283
124-284
124-285
124-286
124-287
124-288
124-289
124-290
124-291
124-292
124-293
124-294
124-295
124-296
124-297
124-298
124-299
124-300
124-301
124-302
124-303
124-304
124-305
124-306
124-307
124-308
124-309
124-310
124-311
124-312
124-313
124-314
124-315
124-316
124-317
124-318
124-319
124-320
124-321
124-322
124-323
124-324
124-325
124-326
124-327
124-328
124-329
124-330
124-331
124-332
124-333
124-334
124-335
124-336
124-337
124-338
124-339
124-340
124-341
124-342
124-343
124-344
124-345
124-346
124-347
124-348
124-349
124-350
124-351
124-352
124-353
124-354
124-355
124-356
124-357
124-358
124-359
124-360
124-361
124-362
124-363
124-364
124-365
124-366
124-367
124-368
124-369
124-370
124-371
124-372
124-373
124-374
124-375
124-376
124-377
124-378
124-379
124-380
124-381
124-382
124-383
124-384
124-385
124-386
124-387
124-388
124-389
124-390
124-391
124-392
124-393
124-394
124-395
124-396
124-397
124-398
124-399
124-400
124-401
124-402
124-403
124-404
124-405
124-406
124-407
124-408
124-409
124-410
124-411
124-412
124-413
124-414
124-415
124-416
124-417
124-418
124-419
124-420
124-421
124-422
124-423
124-424
124-425
124-426
124-427
124-428
124-429
124-430
124-431
124-432
124-433
124-434
124-435
124-436
124-437
124-438
124-439
124-440
124-441
124-442
124-443
124-444
124-445
124-446
124-447
124-448
124-449
124-450
124-451
124-452
124-453
124-454
124-455
124-456
124-457
124-458
124-459
124-460
124-461
124-462
124-463
124-464
124-465
124-466
124-467
124-468
124-469
124-470
124-471
124-472
124-473
124-474
124-475
124-476
124-477
124-478
124-479
124-480
124-481
124-482
124-483
124-484
124-485
124-486
124-487
124-488
124-489
124-490
124-491
124-492
124-493
124-494
124-495
124-496
124-497
124-498
124-499
124-500
124-501
124-502
124-503
124-504
124-505
124-506
124-507
124-508
124-509
124-510
124-511
124-512
124-513
124-514
124-515
124-516
124-517
124-518
124-519
124-520
124-521
124-522
124-523
124-524
124-525
124-526
124-527
124-528
124-529
124-530
124-531
124-532
124-533
124-534
124-535
124-536
124-537
124-538
124-539
124-540
124-541
124-542
124-543
124-544
124-545
124-546
124-547
124-548
124-549
124-550
124-551
124-552
124-553
124-554
124-555
124-556
124-557
124-558
124-559
124-560
124-561
124-562
124-563
124-564
124-565
124-566
124-567
124-568
124-569
124-570
124-571
124-572
124-573
124-574
124-575
124-576
124-577
124-578
124-579
124-580
124-581
124-582
124-583
124-584
124-585
124-586
124-587
124-588
124-589
124-590
124-591
124-592
124-593
124-594
124-595
124-596
124-597
124-598
124-599
124-600
124-601
124-602
124-603
124-604
124-605
124-606
124-607
124-608
124-609
124-610
124-611
124-612
124-613
124-614
124-615
124-616
124-617
124-618
124-619
124-620
124-621
124-622
124-623
124-624
124-625
124-626
124-627
124-628
124-629
124-630
124-631
124-632
124-633
124-634
124-635
124-636
124-637
124-638
124-639
124-640
124-641
124-642
124-643
124-644
124-645
124-646
124-647
124-648
124-649
124-650
124-651
124-652
124-653
124-654
124-655
124-656
124-657
124-658
124-659
124-660
124-661
124-662
124-663
124-664
124-665
124-666
124-667
124-668
124-669
124-670
124-671
124-672
124-673
124-674
124-675
124-676
124-677
124-678
124-679
124-680
124-681
124-682
124-683
124-684
124-685
124-686
124-687
124-688
124-689
124-690
124-691
124-692
124-693
124-694
124-695
124-696
124-697
124-698
124-699
124-700
124-701
124-702
124-703
124-704
124-705
124-706
124-707
124-708
124-709
124-710
124-711
124-712
124-713
124-714
124-715
124-716
124-717
124-718
124-719
124-720
124-721
124-722
124-723
124-724
124-725
124-726
124-727
124-728
124-729
124-730
124-731
124-732
124-733
124-734
124-735
124-736
124-737
124-738
124-739
124-740
124-741
124-742
124-743
124-744
124-745
124-746
124-747
124-748
124-749
124-750
124-751
124-752
124-753
124-754
124-755
124-756
124-757
124-758
124-759
124-760
124-761
124-762
124-763
124-764
124-765
124-766
124-767
124-768
124-769
124-770
124-771
124-772
124-773
124-774
124-775
124-776
124-777
124-778
124-779
124-780
124-781
124-782
124-783
124-784
124-785
124-786
124-787
124-788
124-789
124-790
124-791
124-792
124-793
124-794
124-795
124-796
124-797
124-798
124-799
124-800
124-801
124-802
124-803
124-804
124-805
124-806
124-807
124-808
124-809
124-810
124-811
124-812
124-813
124-814
124-815
124-816
124-817
124-818
124-819
124-820
124-821
124-822
124-823
124-824
124-825
124-826
124-827
124-828
124-829
124-830
124-831
124-832
124-833
124-834
124-835
124-836
124-837
124-838
124-839
124-840
124-841
124-842
124-843
124-844
124-845
124-846
124-847
124-848
124-849
124-850
124-851
124-852
124-853
124-854
124-855
124-856
124-857
124-858
124-859
124-860
124-861
124-862
124-863
124-864
124-865
124-866
124-867
124-868
124-869
124-870
124-871
124-872
124-873
124-874
124-875
124-876
124-877
124-878
124-879
124-880
124-881
124-882
124-883
124-884
124-885
124-886
124-887
124-888
124-889
124-890
124-891
124-892
124-893
124-894
124-895
124-896
124-897
124-898
124-899
124-900
124-901
124-902
124-903
124-904
124-905
124-906
124-907
124-908
124-909
124-910
124-911
124-912
124-913
124-914
124-915
124-916
124-917
124-918
124-919
124-920
124-921
124-922
124-923
124-924
124-925
124-926
124-927
124-928
124-929
124-930
124-931
124-932
124-933
124-934
124-935
124-936
124-937
124-938
124-939
124-940
124-941
124-942
124-943
124-944
124-945
124-946
124-947
124-948
124-949
124-950
124-951
124-952
124-953
124-954
124-955
124-956
124-957
124-958
124-959
124-960
124-961
124-962
124-963
124-964
124-965
124-966
124-967
124-968
124-969
124-970
124-971
124-972
124-973
124-974
124-975
124-976
124-977
124-978
124-979
124-980
124-981
124-982
124-983
124-984
124-985
124-986
124-987
124-988
124-989
124-990
124-991
124-992
124-993
124-994
124-995
124-996
124-997
124-998
124-999
125-000
125-001
125-002
125-003
125-004
125-005
125-006
125-007
125-008
125-009
125-010
125-011
125-012
125-013
125-014
125-015
125-016
125-017
125-018
125-019
125-020
125-021
125-022
125-023
125-024
125-025
125-026
125-027
125-028
125-029
125-030
125-031
125-032
125-033
125-034
125-035
125-036
125-037
125-038
125-039
125-040
125-041
125-042
125-043
125-044
125-045
125-046
125-047
125-048
125-049
125-050
125-051
125-052
125-053
125-054
125-055
125-056
125-057
125-058
125-059
125-060
125-061
125-062
125-063
125-064
125-065
125-066
125-067
125-068
125-069
125-070
125-071
125-072
125-073
125-074
125-075
125-076
125-077
125-078
125-079
125-080
125-081
125-082
125-083
125-084
125-085
125-086
125-087
125-088
125-089
125-090
125-091
125-092
125-093
125-094
125-095
125-096
125-097
125-098
125-099
125-100
125-101
125-102
125-103
125-104
125-105
125-106
125-107
125-108
125-109
125-110
125-111
125-112
125-113
125-114
125-115
125-116
125-117
125-118
125-119
125-120
125-121
125-122
125-123
125-124
125-125
125-126
125-127
125-128
125-129
125-130
125-131
125-132
125-133
125-134
125-135
125-136
125-137
125-138
125-139
125-140
125-141
125-142
125-143
125-144
125-145
125-146
125-147
125-148
125-149
125-150
125-151
125-152
125-153
125-154
125-155
125-156
125-157
125-158
125-159
125-160
125-161
125-162
125-163
125-164
125-165
125-166
125-167
125-168
125-169
125-170
125-171
125-172
125-173
125-174
125-175
125-176
125-177
125-178
125-179
125-180
125-181
125-182
125-183
125-184
125-185
125-186
125-187
125-188
125-189
125-190
125-191
125-192
125-193
125-194
125-195
125-196
125-197
125-198
125-199
125-200
125-201
125-202
125-203
125-204
125-205
125-206
125-207
125-208
125-209
125-210
125-211
125-212
125-213
125-214
125-215
125-216
125-217
125-218
125-219
125-220
125-221
125-222
125-223
125-224
125-225
125-226
125-227
125-228
125-229
125-230
125-231
125-232
125-233
125-234
125-235
125-236
125-237
125-238
125-239
125-240
125-241
125-242
125-243
125-244
125-245
125-246
125-247
125-248
125-249
125-250
125-251
125-252
125-253
125-254
125-255
125-256
125-257
125-258
125-259
125-260
125-261
125-262
125-263
125-264
125-265
125-266
125-267
125-268
125-269
125-270
125-271
125-272
125-273
125-274
125-275
125-276
125-277
125-278
125-279
125-280
125-281
125-282
125-283
125-284
125-285
125-286
125-287
125-288
125-289
125-290
125-291
125-292
125-293
125-294
125-295
125-296
125-297
125-298
125-299
125-300
125-301
125-302
125-303
125-304
125-305
125-306
125-307
125-308
125-309
125-310
125-311
125-312
125-313
125-314
125-315
125-316
125-317
125-318
125-319
125-320
125-321
125-322
125-323
125-324
125-325
125-326
125-327
125-328
125-329
125-330
125-331
125-332
125-333
125-334
125-335
125-336
125-337
125-338
125-339
125-340
125-341
125-342
125-343
125-344
125-345
125-346
125-347
125-348
125-349
125-350
125-351
125-352
125-353
125-354
125-355
125-356
125-357
125-358
125-359
125-360
125-361
125-362
125-363
125-364
125-365
125-366
125-367
125-368
125-369
125-370
125-371
125-372
125-373
125-374
125-375
125-376
125-377
125-378
125-379
125-380
125-381
125-382
125-383
125-384
125-385
125-386
125-387
125-388
125-389



THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
 HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - NAD 83 AND MEETS NATIONAL MAP ACCURACY STANDARDS.
 GPS CONTROL BY: COLE & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC.
 PHOTOGRAPHY BY: CHAS. H. SELLS, INC.
 PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT); MAY 9, 1992 (1"=2000' FLIGHT)
 COMPLETION DATE: APRIL 15, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
 PROFESSIONAL CONSULTANTS
 MUNICIPAL MAPPING - GIS - LAND SURVEYING
 12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561
 (603)444-6788 - (800)322-4540 - FAX (603)444-1368

AREA SURVEYED AC
 AREA CALCULATED AC
 RECORD DIMENSION 100'
 SCALED DIMENSION 100'S
 COMMON OWNERSHIP OR

LEGEND
 MATCH LINE M.L.
 RIGHT OF WAY R/W
 SURFACE WATER W
 WETLANDS W

TAX EXEMPT PROPERTY
 SUBDIVISION LOT NO.
 BUILDING
 LOT/RANGE
 BLOCK NUMBER B25


FEET SCALE 1" = 400'
 0 200 400 600 800 1000 1200
 METERS
 REVISED TO: April 1, 1999

PROPERTY MAP
BERLIN
 NEW HAMPSHIRE
 CONTRACTING AUTHORITY: CITY OF BERLIN
 CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ

INDEX DIAGRAM
 402|403|404
 407|408|409
 410|411|412
 MAP NO.
406

LEGEND

RR - RURAL RESIDENTIAL
 RS - RESIDENTIAL SINGLE FAMILY
 RT - RESIDENTIAL TWO FAMILY
 RG - RESIDENTIAL GENERAL
 DT - DOWNTOWN
 BG - BUSINESS GENERAL
 IB - INDUSTRIAL/BUSINESS





**CITY OF BERLIN
 ZONING MAP**

ADOPTED BY
 BERLIN CITY COUNCIL
 NOVEMBER 1, 1999

PREPARED FOR
 BERLIN PLANNING DEPARTMENT

BY
 YORK LAND SERVICES CO.
 2 TOWN OF STREETS
 BERLIN, MD 20840
 410-352-7282



THIS MAP IS FOR ASSESSMENT PURPOSES. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
 THE HORIZONTAL DATUM IS THE NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM.
 PHOTOGRAPHY DATE: MARCH 29, 1992
 COMPLETION DATE: APRIL 15, 1993

PRODUCED IN 1993 BY
CARTOGRAPHIC ASSOC. INC.
 PROFESSIONAL CONSULTANTS
 MUNICIPAL MAPPING - GIS - LAND SURVEYING
 12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03561
 (603)444-6788 - (800)322-4540 - FAX (603)444-1366


LEGEND
 100' 1" = 100' SCALE MAP
 APPROXIMATE CENTER OF 100' SCALE PHOTO ENLARGEMENT
 400' 1" = 400' SCALE MAP
 APPROXIMATE CENTER OF 400' SCALE PHOTO ENLARGEMENT
 COORDINATE VALUE OF NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM

MAP SCALE AS NOTED ABOVE


REVISED TO: April 1, 1999

PROPERTY MAPS
BERLIN
 NEW HAMPSHIRE


INDEX MAP




<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - NAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL BY: COLOR & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC.</p> <p>PHOTOGRAMMETRY BY: CHAS. H. SELLS, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 29, 1992 (1"=750' FLIGHT); MAY 9, 1992 (1"=2000' FLIGHT)</p> <p>COMPLETION DATE: APRIL 15, 1993</p>	<p>PRODUCED IN 1993 BY CARTOGRAPHIC ASSOC. INC. PROFESSIONAL CONSULTANTS MUNICIPAL MAPPING - GIS - LAND SURVEYING 12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03581 (603)444-6768 - (800)322-454C - FAX (603)444-1386</p>		<p>LEGEND</p> <p>AREA SURVEYED Ac</p> <p>AREA CALCULATED Ac</p> <p>RECORD DIMENSION 100'</p> <p>SCALED DIMENSION 100'</p> <p>COMMON OWNERSHIP OR</p> <p>MATCH LINE M.L.</p> <p>RIGHT OF WAY R/W</p> <p>SURFACE WATER -W-</p> <p>METLANDS M.L.</p>	<p>TAX EXEMPT PROPERTY B25</p> <p>SUBDIVISION LOT NO.</p> <p>BUILDING B25</p> <p>LOT/RANGE B25</p> <p>BLOCK NUMBER B25</p>	<p>FEET SCALE 1" = 100'</p> <p>0 50 100 150 200 250 300</p> <p>METERS</p> <p>REVISED TO: April 1, 1999</p>	<p>PROPERTY MAP BERLIN NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ</p>	<p>INDEX DIAGRAM</p> <p>104 105 106 107 108</p> <p>406 407 408</p> <p>410 107 108</p>	<p>MAP NO. 106</p>
--	---	--	---	---	--	--	---	-------------------------------




<p>THIS MAP IS FOR ABSTRACT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OF CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - NAD 83 AND METRIC NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL: DR. COLLETT & COLLETT, INC. & CARTOGRAPHIC ASSOCIATES, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT); MAY 8, 1992 (1"=2000' FLIGHT)</p> <p>COMPLETION DATE: APRIL 15, 1993</p>		<p>PRODUCED IN 1993 BY</p> <p>CARTOGRAPHIC ASSOC. INC.</p> <p>PROFESSIONAL CONSULTANTS</p> <p>MUNICIPAL MAPPING - GIS - LAND SURVEYING</p> <p>12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03561</p> <p>(603)444-8768 - (800)322-4540 - FAX (603)444-1366</p>		<p>LEGEND</p> <p>M.L. MATCH LINE</p> <p>RIGHT OF WAY</p> <p>SURFACE WATER</p> <p>WETLANDS</p> <p>TAX EXEMPT PROPERTY</p> <p>SUBDIVISION LOT NO.</p> <p>BUILDING</p> <p>LOT/RANGE</p> <p>BLOCK NUMBER</p>		<p>FEET SCALE 1" = 100'</p> <p>METERS</p> <p>REVISOR TO April 1, 1997</p>		<p>PROPERTY MAP</p> <p>BERLIN</p> <p>NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN</p> <p>CONTRACTING OFFICIAL: CITY MANAGER - WITHELL BERNHART</p>		<p>INDEX DIAGRAM</p> <p>MAP NO. 113</p>	
---	--	--	--	--	--	---	--	---	--	---	--



<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - MASS 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL BY: COLLIER & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC.</p> <p>PHOTOGRAMMETRY BY: CHAS. H. BELL, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT); MAY 11, 1992 (1"=2000' FLIGHT)</p> <p>COMPLETION DATE: APRIL 15, 1993</p>		<p>PRODUCED IN 1993 BY</p> <p>CARTOGRAPHIC ASSOC. INC.</p> <p>PROFESSIONAL CONSULTANTS</p> <p>MUNICIPAL MAPPING - GIS - LAND SURVEYING</p> <p>12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03561</p> <p>(603)444-8768 - (603)322-4540 - FAX (603)444-1368</p>		<p>AREA SURVEYED Ac</p> <p>AREA CALCULATED Ac</p> <p>RECORD DIMENSION 100'</p> <p>SCALE DIMENSION 100'</p> <p>COMMON OWNERSHIP</p>		<p>LEGEND</p> <p>M.L.</p> <p>S.W.</p> <p>RIGHT OF WAY</p> <p>SURFACE WATER</p> <p>WETLANDS</p>		<p>TAX EXEMPT PROPERTY</p> <p>SUBDIVISION LOT NO.</p> <p>BUILDING</p> <p>LOT/RANGE</p> <p>BLOCK NUMBER B25</p>		<p>FEET SCALE 1" = 100'</p> <p>0 50 100 200 300</p> <p>METERS</p> <p>0 25 50 75</p> <p>REVISED TO April 1, 1997</p>		<p>PROPERTY MAP</p> <p>BERLIN</p> <p>NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN</p> <p>CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BOWEN</p>		<p>INDEX DIAGRAM</p> <p>414 113 116</p> <p>115</p> <p>414</p>		<p>MAP NO.</p> <p>114</p>	
---	--	--	--	--	--	--	--	--	--	---	--	---	--	---	--	----------------------------------	--



<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - NAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL BY COLER & COLANTONIO, INC. & CARTOGRAPHIC ASSOCIATES INC. PHOTOGRAMMETRY BY CHAS. H. SELLS, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=750' FLIGHT); MAY 9, 1992 (1"=2000' FLIGHT)</p> <p>COMPLETION DATE: APRIL 13, 1993</p>	<p>PRODUCED IN 1993 BY CARTOGRAPHIC ASSOC. INC.</p> <p>PROFESSIONAL CONSULTANTS MUNICIPAL MAPPING - GIS - LAND SURVEYING 12 PLEASANT STREET, P.O. BOX 257, LITTLETON, NEW HAMPSHIRE 03561 (603)444-0768 - (603)222-4540 - FAX (603)444-1366</p>	<p>AREA SURVEYED AC</p> <p>AREA CALCULATED AC</p> <p>RECORD DIMENSION 100'</p> <p>SCALED DIMENSION 100'S</p> <p>COMMON OWNERSHIP ON</p>	<p>LEGEND</p> <p>M.L. MATCH LINE</p> <p>R/W RIGHT OF WAY</p> <p>SW SURFACE WATER</p> <p>W- WETLANDS</p> <p>TAX EXEMPT PROPERTY</p> <p>SUBDIVISION LOT NO.</p> <p>BUILDING</p> <p>LOT/RANGE</p> <p>BLOCK NUMBER</p> <p>B25</p>	<p>FEET SCALE 1" = 100'</p> <p>0 50 100 200 300</p> <p>METERS</p> <p>0 25 50 75</p> <p>REVISED TO: APRIL 1, 1999</p>	<p>PROPERTY MAP BERLIN NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN</p> <p>CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ</p>	<p>INDEX DIAGRAM</p> <p>112 117 131</p> <p>113 414</p> <p>114 115</p>	<p>MAP NO. 116</p>
---	--	---	---	--	---	---	-------------------------------



<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.</p> <p>HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - MAD 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.</p> <p>GPS CONTROL BY: CULLEN & COLANDRINO, INC. & CARTOGRAPHIC ASSOCIATES, INC.</p> <p>PHOTOGRAMMETRY BY: CHAS. N. ZELLS, INC.</p> <p>PHOTOGRAPHY DATE: APRIL 23, 1992 (1"=750' FLIGHT); MAY 6, 1992 (1"=2000' FLIGHT)</p> <p>COMPLETION DATE: APRIL 15, 1993</p>		<p>PRODUCED IN 1993 BY CARTOGRAPHIC ASSOC. INC. PROFESSIONAL CONSULTANTS MUNICIPAL MAPPING - GIS - LAND SURVEYING 12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561 (603)444-6768 - (800)322-4540 - FAX (603)444-1368</p>		<p>AREA SURVEYED.....Ac AREA CALCULATED.....Ac RECORD DIMENSION.....100' SCALED DIMENSION.....100'S COMMON OWNERSHIP.....OR</p>		<p>LEGEND</p> <p>MATCH LINE.....M.L. RIGHT OF WAY.....R/W SURFACE WATER.....-W- WETLANDS.....W</p>		<p>TAX EXEMPT PROPERTY..... SUBDIVISION LOT NO..... BUILDING..... LOT/RANGE..... BLOCK NUMBER.....B25</p>		<p>FEET SCALE 1" = 100' 0 50 100 200 300 METERS</p> <p>REVISED TO: April 1, 1999</p>		<p>PROPERTY MAP BERLIN NEW HAMPSHIRE</p> <p>CONTRACTING AUTHORITY: CITY OF BERLIN CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ</p>		<p>INDEX DIAGRAM</p> <p>111 118 130 112 119 131 113 116 414</p>		<p>MAP NO. 117</p>	
--	--	---	--	---	--	--	--	---	--	--	--	--	--	---	--	-------------------------------	--



<p>THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION.</p> <p>HORIZONTAL DATUM IS THE N.H. STATE PLANE COORDINATE SYSTEM - NAD 1983 AND VERTICES NATIONAL MAP ACCURACY STANDARDS.</p> <p>CPS CONTROL, ITS COLOR & COORDINATES, INC. & CARTOGRAPHIC ASSOCIATES INC.</p> <p>PHOTOGRAPHY DATE: APRIL 29, 1992 (1"=750' FLIGHT) MAY 9, 1992 (1"=2000' FLIGHT)</p>		<p>PRODUCED IN 1993 BY CARTOGRAPHIC ASSOC. INC. PROFESSIONAL CONSULTANTS MUNICIPAL MAPPING - GIS - LAND SURVEYING 12 PLEASANT STREET, P.O. BOX 267, LITTLETON, NEW HAMPSHIRE 03551 (603)444-6768 - (603)322-4540 - FAX (603)444-1366</p>		<p>AREA SURVEYED AC AREA CALCULATED AC RECORD DIMENSION 100' SCALED DIMENSION 100' COMMON OWNERSHIP OR</p> <p>LEGEND M.L. → WATCH LINE RIGHT OF WAY SURFACE WATER WETLANDS TAX EXEMPT PROPERTY SUBDIVISION LOT NO. BUILDING LOT/RANGE BLOCK NUMBER B25</p>		<p>FEET SCALE 1" = 100' 0 100 200 300 METERS</p> <p>REVISED TO: April 1, 1999</p>		<p>PROPERTY MAP BERLIN NEW HAMPSHIRE CONTRACTING AUTHORITY: CITY OF BERLIN CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BURNHART</p>		<p>INDEX DIAGRAM 122/126/136 121/135 120/128/134</p>		<p>MAP NO. 127</p>	
--	--	---	--	--	--	---	--	--	--	--	--	-------------------------------	--



THIS MAP IS FOR ASSESSMENT PURPOSES ONLY. IT IS NOT VALID FOR LEGAL DESCRIPTION OR CONVEYANCE.
HORIZONTAL DATUM IS THE NAD 83 STATE PLANE COORDINATE SYSTEM - MARS 1983 AND MEETS NATIONAL MAP ACCURACY STANDARDS.
GPS CONTROL BY: COLONY, INC. & CARTOGRAPHIC ASSOCIATES, INC.
PHOTOGRAPHY BY: CHAS. H. SELLS, INC.
PHOTOGRAPHY DATE: APRIL 28, 1992 (1"=700' FLIGHT); MAY 9, 1992 (1"=2000' FLIGHT)
COMPLETION DATE: APRIL 15, 1993

PRODUCED IN BY
CARTOGRAPHIC ASSOC. NC.
PROFESSIONAL CONSULTANTS
MUNICIPAL MAPPING - GIS - LAND SURVEYING
12 PLEASANT STREET, P.O. BOX 287, LITTLETON, NEW HAMPSHIRE 03561
(603) 444-8788 - (800) 322-4540 - FAX (603) 444-1368

AREA SURVEYED AC
AREA CALCULATED AC
RECORD DIMENSION 100'
SCALED DIMENSION 100%
COMMON OWNERSHIP ON

LEGEND
MATCH LINE
RIGHT OF WAY
SURFACE WATER
WETLANDS

FEET SCALE 1" = 100'
METERS
REVISED TO: April 1, 1993

PROPERTY MAP
BERLIN
NEW HAMPSHIRE
CONTRACTING AUTHORITY: CITY OF BERLIN
CONTRACTING OFFICIAL: CITY MANAGER - MITCHELL BERKOWITZ

INDEX DIAGRAM
121 127 135
120 134
119 129 133
MAP NO.
128

Tier Two Continuation Form

Chemical Description THE CHEMICAL NAME MUST BE IN ALPHABETICAL ORDER PLEASE	Physical and Health Hazards SEE INSTRUCTION PAGE 3	Inventory SEE INSTRUCTION PAGE 3 & 4	Storage Codes SEE INSTRUCTION PAGE 4	STORAGE LOCATIONS SEE INSTRUCTION PAGE 5 Only 105 characters available including word spaces (Please Print)
<input checked="" type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text"/> <input type="text"/> <input type="text"/> 1 2 7 <input type="text"/> <input type="text"/> 1 8 4 Trade Secret <input type="checkbox"/> Chem. Name PERCHLOROETHYLENE EHS Name _____ Check all that apply: <input type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input checked="" type="checkbox"/> Delayed (chronic)	0 4 Max. Daily Amount (code) 0 4 Avg. Daily Amount (code) 3 6 5 No. of Days On-site (days)	Container Type Pressure Temperature C 1 4 C 1 5 C 1 5 C 1 5 C 1 5 C 1 5	PCB STORAGE VAULT SERVICE GARAGE DRYER AREA NE AND SW CORNERS PULP DRYER BUILDING #11 CRU BUILDING NORTH WALL RECOVERY AREA BASEMENT #8 CRU (3 TRANSFORMERS) RECOVERY AREA LIME KILN EAST AND WEST ENDS LIME KILN BUILDING DIESTER BUILDING NORTH END PULPING AREA
<input checked="" type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text"/> <input type="text"/> <input type="text"/> 1 2 7 <input type="text"/> <input type="text"/> 1 8 4 Trade Secret <input type="checkbox"/> Chem. Name PERCHLOROETHYLENE EHS Name _____ Check all that apply: <input type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input checked="" type="checkbox"/> Delayed (chronic)	0 4 Max. Daily Amount (code) 0 4 Avg. Daily Amount (code) 3 6 5 No. of Days On-site (days)	Container Type Pressure Temperature C 1 5 C 1 5	SCREENS AND BLOW PIT'S PULPING AREA MACHINE SHOP 2ND FLOOR BURGESS MAINTENANCE
<input type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> <input type="text"/> Trade Secret <input type="checkbox"/> Chem. Name PERCOL 175 EHS Name _____ Check all that apply: <input checked="" type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input checked="" type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input type="checkbox"/> Delayed (chronic)	0 4 Max. Daily Amount (code) 0 3 Avg. Daily Amount (code) 3 6 5 No. of Days On-site (days)	Container Type Pressure Temperature C 1 4 J 1 4	BURGESS WWTP BWWTP BURGESS WWTP BWWTP
<input type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text"/> <input type="text"/> 7 8 6 4 <input type="text"/> <input type="text"/> 3 8 2 Trade Secret <input type="checkbox"/> Chem. Name PHOSPHORIC ACID (62% SOLUTION) EHS Name _____ Check all that apply: <input checked="" type="checkbox"/> Pure <input type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input checked="" type="checkbox"/> Delayed (chronic)	0 5 Max. Daily Amount (code) 0 5 Avg. Daily Amount (code) 3 6 5 No. of Days On-site (days)	Container Type Pressure Temperature A 1 4	NORTHEAST CORNER WWTP BUILDING BWWTP

Tier Two Continuation Form

Chemical Description THE CHEMICAL NAME MUST BE IN ALPHABETICAL ORDER PLEASE	Physical and Health Hazards SEE INSTRUCTION PAGE 3	Inventory SEE INSTRUCTION PAGE 3 & 4	Storage Codes SEE INSTRUCTION PAGE 4	STORAGE LOCATIONS SEE INSTRUCTION PAGE 6 Only 105 characters available including word spaces (Please Print)																		
<input checked="" type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text" value="1"/> <input type="text" value="2"/> <input type="text" value="6"/> <input type="text" value="7"/> <input type="text" value="2"/> <input type="text" value="2"/> <input type="text" value="9"/> <input type="text" value="6"/> Trade Secret <input type="checkbox"/> Chem. Name POLYCHLORINATED BIPHENYLS (PCB) EHS Name _____ Check all that apply: <input type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input checked="" type="checkbox"/> Delayed (chronic)	<input type="text" value="0"/> <input type="text" value="2"/> Max. Daily Amount (code) <input type="text" value="0"/> <input type="text" value="2"/> Avg. Daily Amount (code) <input type="text" value="3"/> <input type="text" value="6"/> <input type="text" value="5"/> No. of Days On-site (days)	Container Type Pressure Temperature <table border="1"> <tr><td>C</td><td>1</td><td>4</td></tr> <tr><td>C</td><td>1</td><td>5</td></tr> <tr><td>C</td><td>1</td><td>6</td></tr> <tr><td>C</td><td>1</td><td>5</td></tr> <tr><td>C</td><td>1</td><td>6</td></tr> <tr><td>C</td><td>1</td><td>6</td></tr> </table>	C	1	4	C	1	5	C	1	6	C	1	5	C	1	6	C	1	6	PCB STORAGE VAULT SERVICE GARAGE DRYER AREA SW CORNER PULP DRYER BUILD DING DRYER AREA NE CORNER PULP DRYER BUILD DING #11 CRU BUILDING N WALL RECOVERY AREA A BASEMENT #6 CRU (3 TRANSFORMERS) RECOVERY AREA LIME KILN AND W ENDS OF BUILDING LIME KILN
C	1	4																				
C	1	5																				
C	1	6																				
C	1	5																				
C	1	6																				
C	1	6																				
<input checked="" type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text" value="1"/> <input type="text" value="2"/> <input type="text" value="6"/> <input type="text" value="7"/> <input type="text" value="2"/> <input type="text" value="2"/> <input type="text" value="9"/> <input type="text" value="6"/> Trade Secret <input type="checkbox"/> Chem. Name POLYCHLORINATED BIPHENYLS (PCB) EHS Name _____ Check all that apply: <input type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input checked="" type="checkbox"/> Delayed (chronic)	<input type="text" value="0"/> <input type="text" value="2"/> Max. Daily Amount (code) <input type="text" value="0"/> <input type="text" value="2"/> Avg. Daily Amount (code) <input type="text" value="3"/> <input type="text" value="6"/> <input type="text" value="5"/> No. of Days On-site (days)	Container Type Pressure Temperature <table border="1"> <tr><td>C</td><td>1</td><td>5</td></tr> <tr><td>C</td><td>1</td><td>5</td></tr> <tr><td>C</td><td>1</td><td>5</td></tr> <tr><td>C</td><td>1</td><td>6</td></tr> </table>	C	1	5	C	1	5	C	1	5	C	1	6	DIGESTER BUILDING N END PULPING AREA SCREENS AND BLOW PITS PULPING AREA MACHINE SHOP 2ND FLOOR BURGESS MAINTENANCE TURBINE BASEMENT CENTRAL STEAM						
C	1	5																				
C	1	5																				
C	1	5																				
C	1	6																				
<input type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text" value="7"/> <input type="text" value="7"/> <input type="text" value="7"/> <input type="text" value="5"/> <input type="text" value="0"/> <input type="text" value="9"/> <input type="text" value="9"/> Trade Secret <input type="checkbox"/> Chem. Name SODIUM CHLORATE (SOLID) EHS Name _____ Check all that apply: <input checked="" type="checkbox"/> Pure <input type="checkbox"/> Mix <input checked="" type="checkbox"/> Solid <input type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input checked="" type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input type="checkbox"/> Delayed (chronic)	<input type="text" value="0"/> <input type="text" value="6"/> Max. Daily Amount (code) <input type="text" value="0"/> <input type="text" value="5"/> Avg. Daily Amount (code) <input type="text" value="3"/> <input type="text" value="6"/> <input type="text" value="5"/> No. of Days On-site (days)	Container Type Pressure Temperature <table border="1"> <tr><td>Q</td><td>1</td><td>4</td></tr> </table>	Q	1	4	CHLORATE UNLOADING AREA BLEACH PLANT															
Q	1	4																				
<input checked="" type="checkbox"/> CHECK IF CHEMICAL INFORMATION IN THIS AREA IS IDENTICAL TO THE INFORMATION LISTED LAST YEAR. CAS <input type="text" value="7"/> <input type="text" value="7"/> <input type="text" value="7"/> <input type="text" value="5"/> <input type="text" value="0"/> <input type="text" value="9"/> <input type="text" value="9"/> Trade Secret <input type="checkbox"/> Chem. Name SODIUM CHLORATE (SOLUTION) EHS Name _____ Check all that apply: <input type="checkbox"/> Pure <input checked="" type="checkbox"/> Mix <input type="checkbox"/> Solid <input checked="" type="checkbox"/> Liquid <input type="checkbox"/> Gas <input type="checkbox"/> EHS	<input type="checkbox"/> Fire <input type="checkbox"/> Sudden Release of Pressure <input type="checkbox"/> Reactivity <input checked="" type="checkbox"/> Immediate (acute) <input type="checkbox"/> Delayed (chronic)	<input type="text" value="0"/> <input type="text" value="5"/> Max. Daily Amount (code) <input type="text" value="0"/> <input type="text" value="5"/> Avg. Daily Amount (code) <input type="text" value="3"/> <input type="text" value="6"/> <input type="text" value="5"/> No. of Days On-site (days)	Container Type Pressure Temperature <table border="1"> <tr><td>A</td><td>1</td><td>5</td></tr> </table>	A	1	5	NORTH SIDE OF ALPHA PLANT BLEACH PLANT NT															
A	1	5																				

Current trans Report

Area_resp	Class	Mill no	Location	Gallons	Mfg.
Burgess	NON PCB				
		4	Floc Plant Pole Type	500	Westinghouse
		49	Inst. Roof O/S	25	Pittsburgh
		201	Cross Power stor	0	Stanley
		208	Research	30	GE
		259	Research	30	Westinghouse
		429	Research	91	Westinghouse
		436	Burgess WWTP	265	GE
		439	Burgess 22KV	170	Westinghouse
		463	Motor Repair (Res)	50	GE
		464	Motor Repair (Res)	50	GE
		481	Research	10	Maloney
		491	Research - Sal. Roof	50	GE
		525	Floc Plant Pole type	10	Allis Chalmers
		647	Floc Sub	2230	Pennsylvania
		648	Tractor Shop Storage	2230	Pennsylvania
		675	D C Dam	60	Westinghouse
		676	Floc Plant	60	Westinghouse
		679	Tractor Shop Storage	60	Westinghouse
		680	Car Shop Pole type	10	Westinghouse
		699	Heine Boiler #9	264	Wagner
		703	Tractor Shop Storage	1400	Westinghouse
		710	Central Steam Turbin	1620	Westinghouse
		716	Tractor Shop Storage	723	Westinghouse
		718	Tractor Shop Storage	723	Westinghouse
		726	Floc Hydrogen Sub	200	Maloney
		728	West of Bleachery	1400	Westinghouse
		729	Central Steam Turbin	1620	Westinghouse
		731	Research Basement	GE	
		763	Burgess Main Sub.	1961	Westinghouse
		781	Tractor Shop Storage	1310	Westinghouse
		784	Riverside Hydro	1160	GE
		786	Floc Storage	358	Westinghouse
		787	Tractor Shop Storage	1000	GE
		788	Tractor Shop Storage	557	Westinghouse

Monday, October 29, 2001

Page 1 of 7

<i>Area_resp</i>	<i>Class</i>	<i>Mill no</i>	<i>Location</i>	<i>Gallons</i>	<i>Mfg</i>
		789	#11 Boiler	0	G E
		791	Burgess Area Sub	1220	G E
		793	Trector Shop Storage	600	Westinghouse
		794	#14 Boiler	1008	Westinghouse
		795	#14 Boiler	300	G E
		806	Wood Room Sub	354	Westinghouse
		807	New Bleachery	345	Westinghouse
		808	Pulp Mill	175	Westinghouse
		809	Pulp Mill	175	Westinghouse
		812	Burgess WWTP	500	Magnetic
		815	Kraft Mill	623	Westinghouse
		816	Kraft Mill Riverbank	623	Westinghouse
		817	#1 Bleach Plant	386	Westinghouse
		818	#11 CRU	267	ABB
		819	#11 CRU	267	ABB
		9991	Floc Plant (Mill)	10	
		9999	Floc Plant (Sub)	10	

*Total NON PCB**27508 Gallons**PCB*

582	Main Kraft Mill Sub.	450	G E
583	Main Kraft Mill Sub.	450	G E
584	Main Kraft Mill Sub.	460	G E
635	Ser Garage Vault	286	G E
686	Kraft Screen	425	G E
696	#2 Dryer	425	G E
697	Lg Blow Pit Sub	425	G E
712	Central Steam	10	Westinghouse
714	Lg Blow Pit Sub	515	Westinghouse
727	Sm Blow Pit Sub	515	Westinghouse
745	Horse Shoe Court	380	G E
764	Pulp Mill	294	Westinghouse
767	IMPCO Washer Sub	294	Westinghouse
768	#11 Boiler Sub	411	Westinghouse
769	Ser Garage Vault	289	Westinghouse
770	Kraft Causticizing	289	Westinghouse
771	Kraft Causticizing	289	Westinghouse
774	Ser Garage Vault	187	G E

*Monday, October 29, 2001**Page 2 of 7*

<i>Area resp</i>	<i>Class</i>	<i>Mill no</i>	<i>Location</i>	<i>Gallons</i>	<i>Mfg</i>
			<i>Total PCB</i>	6383	<i>Gallons</i>
			<i>PCB CONT</i>		
		779	Burgess Area	760	Westinghouse
			<i>Total PCB CONT</i>	760	<i>Gallons</i>
			<i>Total for Burgess</i>	34651	<i>Gallons</i>

Section II - BURGESS OIL TANKS

Tank Number	Identity	Contents	Capacity (Gal)
B01	Central Steam Bulk Tank	#6 Fuel Oil	500000
B02	Central Steam Day Tank	#6 Fuel Oil	14000
B03	Central Steam #2 Oil Tank	#2 Oil or Waste Oil	1000
B04	Central Steam Fuel Additive	Waste Oil	5000
B05	#11 Bulk Storage Tank	#6 Fuel Oil	192500
B06	Lime kiln Tank	#6 Fuel Oil	30000
B07	Woodroom #1	Diesel Fuel	1000
B08	Woodroom #2	Diesel Fuel	1000
B09	Windberg Screw	Lube Oil	50
B11	Receiving Deck	Hydraulic Oil	300
B12	Truck Dumper #2	Hydraulic Oil	275
B15	Service Garage #1	Lube/Engine Oil	275
B16	Service Garage #2	Lube/Engine Oil	275
B17	Service Garage #3	Lube/Engine Oil	275
B18	Service Garage #4	Lube/Engine Oil	275
B19	Service Garage #5	Lube/Engine Oil	275
B20	Service Garage Heating Oil #1	#2 Oil	275
B21	Service Garage Heating Oil #2	#2 Oil	275
B22	Service Garage Kerosene	Kerosene	280
B23	Mt Carberry Landfill	Diesel Fuel	1000
B24	Woodyard Scales #1	#2 Oil	300
B25	Woodyard Scales #2	#2 Oil	300
B26	BWWTP	#2 Fuel	1000
B27	#1 Turbine	Lube Oil	450
B28	#4 Turbine	Lube Oil	450
B29	#11 CRU ID Fan	Lube Oil	250
B30	#11 Dryer Bowser System	Lube Oil	2000
B31	Dominion Press	Lube Oil	600
B32	Truck Dumper #2 Hydraulic Storage	Hydraulic Oil	300
B33	Dryer Lube Oil Storage #1	Lube Oil	550
B34	Dryer Lube Oil Storage #2	Lube Oil	550
B35	Valmet Garage Lube #1	Lube Oil	275
B36	Valmet Garage Lube #2	Lube Oil	275
B37	Munce's Diesel Tank	Diesel Fuel	2000
B38	Munce's Gasoline Tank	Unleaded gasoline	3000

760630

Oil Tanks1

<i>Tank Number</i>	<i>Identity</i>	<i>Contents</i>	<i>Capacity (Gal)</i>	<i>Contact Person</i>
ABBWWTP	Absorbent Booms BWW	Are they available?		Lucie Kinney
ABCWWTP	Absorbent Booms CWW	Are they available?		Lucie Kinney
B01	Central Steam Bulk Tan	#6 Fuel Oil	500000	Ray Aube
B02	Central Steam Day Tan	#6 Fuel Oil	14000	Ray Aube
B03	Central Steam #2 Oil Ta	#2 Oil or Waste Oil	1000	Ray Aube
B04	Central Steam Fuel Addl	Waste Oil	5000	Ray Aube
B05	#11 Bulk Storage Tank	#6 Fuel Oil	192500	Carl Belanger
B06	Lime kiln Tank	#6 Fuel Oil	30000	Carl Belanger
B07	Woodroom #1	Diesel Fuel	1000	John Carpenter
B08	Woodroom #2	Diesel Fuel	1000	John Carpenter
B09	Windberg Screw	Lube Oil	50	Ray Aube
B11	Receiving Deck	Hydraulic Oil	300	John Carpenter
B12	Truck Dumper #2	Hydraulic Oil	275	Roger Hayford
B15	Service Garage #1	Lube/Engine Oil	275	Joe Croteau
B16	Service Garage #2	Lube/Engine Oil	275	Joe Croteau
B17	Service Garage #3	Lube/Engine Oil	275	Joe Croteau
B18	Service Garage #4	Lube/Engine Oil	275	Joe Croteau
B19	Service Garage #5	Lube/Engine Oil	275	Joe Croteau
B20	Service Garage Heating	#2 Oil	275	Joe Croteau
B21	Service Garage Heating	#2 Oil	275	Joe Croteau
B22	Service Garage Kerosen	Kerosene	280	Joe Croteau
B23	Mt Carbery Landfill	Diesel Fuel	1000	Dave Marcotte
B24	Woodyard Scales #1	#2 Oil	300	John Carpenter
B25	Woodyard Scales #2	#2 Oil	300	John Carpenter
B26	BWWTP	#2 Fuel	1000	Lucie Kinney
B27	#1 Turbine	Lube Oil	450	Conrad Chevarie
B28	#4 Turbine	Lube Oil	450	Conrad Chevarie
B29	#11 GRU ID Fan	Lube Oil	250	Roger Hayford
B30	#11 Dryer Bowser Syste	Lube Oil	2000	Roger Hayford
B31	Dominion Press	Lube Oil	800	Roger Hayford

<i>Tank Number</i>	<i>Identity</i>	<i>Contents</i>	<i>Capacity (Gal)</i>	<i>Contact Person</i>
B32	Truck Dumper #2 Hydra	Hydraulic Oil	300	Roger Hayford
B33	Dryer Lube Oil Storage	Lube Oil	550	Roger Hayford
B34	Dryer Lube Oil Storage	Lube Oil	550	Roger Hayford
B35	Valmet Garage Lube #1	Lube Oil	275	John Carpenter
B36	Valmet Garage Lube #2	Lube Oil	275	John Carpenter
B37	Munco's Diesel Tank	Diesel Fuel	2000	Joe Croteau
B38	Munco's Gasoline Tank	Unleaded gasoline	3000	Joe Croteau
C02	Cascade Boiler House	Kerosene	275	Leo O'Neill
C03	Cascade Boiler House B	#6 Fuel Oil	150000	Leo O'Neill
C04	Cascade Boiler House D	#6 Fuel Oil	15000	Leo O'Neill
C06	Cascade Maintenance	Diesel Fuel	350	Roger Hayford
C07	Cascade Waste Oil #1	Waste oil	275	Leo O'Neill
C08	Cascade Waste Oil #2	Waste oil	275	Leo O'Neill
C09	Cascade Waste Oil #3	Waste oil	275	Leo O'Neill
C10	Cascade Maintenance	Diesel	275	Roger Hayford
C11	#7 Turbine	Lube Oil	450	Conrad Chevarie
C12	#1 P.M. Bowser	Lube Oil	2750	Roger Hayford
C13	#2 P.M. Bowser	Lube Oil	1500	Roger Hayford
C14	#3 P.M. Bowser	Lube Oil	440	Roger Hayford
C15	#4 P.M. Bowser	Lube Oil	440	Roger Hayford
C16	#5 P.M. Bowser System	Lube Oil	7000	Roger Hayford
C19	#1 PM Calander Stack	Hydraulic Oil	220	Roger Hayford
C20	#2 PM Calander Stack	Hydraulic Oil	220	Roger Hayford
C21	#3 PM Calander Stack	Hydraulic Oil	220	Roger Hayford
C22	#3 PM 2nd Press Hydra	Hydraulic Oil	220	Roger Hayford
C23	#4 PM Calander Stack	Hydraulic Oil	220	Roger Hayford
C24	#4 PM 2nd Press Hydra	Hydraulic Oil	220	Roger Hayford
C25	Lift Station Emergency	Diesel	500	Lucie Kinney
C26	Cascade WWTP Heatin	#2 Fuel	1000	Lucie Kinney
C27	#2 PM 2nd Press Hydra	Hydraulic Oil	75	Roger Hayford
C28	#1 PM Nipco Tri-Press	Hydraulic Oil	330	Roger Hayford
C29	Bowser Bulk Tank	Lube Oil	6250	Roger Hayford
C30	#9 PM Blind Drill Press	Hydraulic Oil	100	Roger Hayford

<i>Tank Number</i>	<i>Identity</i>	<i>Contents</i>	<i>Capacity (Gal)</i>	<i>Contact Person</i>
C31	#9 PM 1st Press Loadin	Hydraulic Oil	100	Roger Hayford
C32	#9 PM Yankee Suction	Hydraulic Oil	100	Roger Hayford
C33	#2 Winder Hydraulics	Hydraulic Oil	110	Roger Hayford
C34	#9 PM Core Puller	Hydraulic Oil	100	Roger Hayford
C35	#9 PM Jumbo Roll Elev	Hydraulic Oil	100	Roger Hayford
C36	#9 PM Jumbo Roll Lowe	Hydraulic Oil	100	Roger Hayford
TB647	Floc Substation T-647	Transformer Oil	2230	Paul Guay
TB648	Tractor Shop Storage T	Transformer Oil	2230	Paul Guay
TB703	Tractor Shop Storage T	Transformer Oil	1400	Paul Guay
TB710	Central Steam Turbine	Transformer Oil	1820	Paul Guay
TB716	Tractor Shop Storage T	Transformer Oil	723	Paul Guay
TB718	Tractor Shop Storage T	Transformer Oil	723	Paul Guay
TB728	West of Bleachery T-72	Transformer Oil	1400	Paul Guay
TB729	Central Steam Turbine	Transformer Oil	1820	Paul Guay
TB763	Burgess Main Sub T-76	Transformer Oil	1961	Paul Guay
TB779	Burgess Area Sub T-77	Transformer Oil	780	Paul Guay
TB781	Tractor Shop Storage T	Transformer Oil	1310	Paul Guay
TB784	Riverside Hydro T-784	Transformer Oil	1160	Paul Guay
TB787	Tractor Shop Storage T	Transformer Oil	1000	Paul Guay
TB791	Burgess Area Sub. T-79	Transformer Oil	1220	Paul Guay
TB794	#14 Boiler T-794	Transformer Oil	1006	Paul Guay
TC595	Cascade Hydro T-595	Transformer Oil	690	Paul Guay
TC596	Cascade Hydro T-596	Transformer Oil	690	Paul Guay
TC631	Cascade Hydro T-631	Transformer Oil	2780	Paul Guay
TC759	Cascade Hydro T-759	Transformer Oil	1195	Paul Guay
TC796	#7 Substation T-796	Transformer Oil	950	Paul Guay
TC797	#7 Substation T-797	Transformer Oil	950	Paul Guay
TC801	#7 Substation T-801	Transformer Oil	946	Paul Guay
TC805	#7 Substation T-805	Transformer Oil	750	Paul Guay
XB10	Air Compressor	Removed 1996	35	
XB13	Truck Dumper #1	Hydraulic Oil	0	
XB14	Dryer	Kerosene - Rem2000	275	
XC01	#10 Paper Machine	#2 Oil - Removed 8/00	25000	

<u>Tank Number</u>	<u>Identity</u>	<u>Contents</u>	<u>Capacity (Gal)</u>	<u>Contact Person</u>
XC05	Boiler House Fuel Additi	Nalco Fuel Tech 7263	400	Leo O'Neill
XC17	#10 P.M. Bowser Syste	Removed 1996	250	
XC18	Cascade WWTP UST	Removed 1996	0	



JAMES RIVER CORPORATION

INTEROFFICE CORRESPONDENCE

DATE October 27, 1987
TO Ray Danforth - Berlin
FROM Dave Edelman - CES/Camas
SUBJECT Reference 869 - Soils PCB Content

ENVIRONMENTAL AFFAIRS

NOV 02 1987

RICHMOND

Samples of soil received here October 26 have been analyzed for trace residues of polychlorinated biphenyls (PCBs). We detect 0.4-2.2 $\mu\text{g/g}$ (ppm) Aroclor 1260 PCBs in the soil samples. Results are shown in Table 1 based upon the samples as received.

Dave Edelman, Jr.

DAVE EDELMAN/kb/1350E

cc:

Frank Vincent - Neenah
Earl Hanson - Richmond

Attachment

TABLE 1

JAMES RIVER CORPORATION - BERLIN/GORHAM GROUPOIL PCB CONTENT

(Reference 869)

<u>Sample Description</u>	<u>PCB Result in ug/g (ppm)</u>					<u>Total Aroclors</u>
	<u>Aroclor 1232</u>	<u>Aroclor 1242</u>	<u>Aroclor 1248</u>	<u>Aroclor 1254</u>	<u>Aroclor 1260</u>	
10/23/87:						
Floc Area #1	ND	ND	ND	ND	0.80	0.80
Floc Area #2	ND	ND	ND	ND	0.78	0.78
Floc Area #3	ND	ND	ND	ND	2.2	2.2
Floc Area #4	ND	ND	ND	ND	0.40	0.40

ND means none detected. Detection limit estimated at 0.2 ug/g (ppm).

Pressure Test* & Replacement Dates of Underground Storage Tanks

Tank #	Contact	Location	Size (Gal)	Date Installed	Type of Liquid	Actual Test Date	Actual Test Date	Test By	Actual Test Date	Test By	Actual Test Date	Replace Tank By
1	J. Marshall	Cascade WWP	4000	1975	# 2 oil	7/14/88	LT	5/9/98				12/31/2000
** 2	Charlie Fysh	Cascade Boiler	25000	pre 1961	# 6 oil	TANK REMOVED 6/26/86 PER STATE OF NH						
** 3	Charlie Fysh	Cascade Boiler	25000	pre 1961	# 6 oil	TANK REMOVED 6/26/86 PER STATE OF NH						
** 4	W. Martin	Service Garage	1000	1970	Gasoline	TANK REMOVED 8/21/86 PER STATE OF NH						
** 5	D. Marcotte	Service Garage	1000	1983	# 2 oil	TANK REMOVED 11/18/92 PER STATE OF NH						
** 6	W. Martin	Service Garage	6000	1965	Gasoline	TANK REMOVED 8/21/86 PER STATE OF NH						
** 7	W. Martin	Service Garage	3000	1969	Diesel	TANK REMOVED 8/21/86 PER STATE OF NH						
** 8	D. Marcotte	Service Garage	500	1983	Used Oil	7/25/89	TANK REMOVED 11/18/92 PER STATE OF NH					
** 9	J. Marshall	Burgess WWP	4000	1975	# 2 oil	7/13/88	TANK REMOVED 7/20/93 PER STATE OF NH					
** 10	G. Etter	B Filter Plant	275	1983	Gasoline	7/13/88	TANK REMOVED 6/4/90 PER STATE OF NH					
11	D. Mercier	Sawmill Hydro	2000	1980	Kerosene	8/15/89	LT	11/9/98		11/2003		12/31/2005
** 12	B. Thomas	Woods-Cambridge	1000	1975	Gasoline	7/14/88	TANK REMOVED 7/20/93 PER STATE OF NH					
** 13	B. Thomas	Woods-Cambridge	1000	1975	Gasoline	7/14/88	TANK REMOVED 7/20/93 PER STATE OF NH					
14	D. Marcotte	Woods-Tractor Shop	3000	1981	Diesel	7/24/89	12/15/92	12/22/94		11/2004		12/31/2006
15	D. Marcotte	Woods-Tractor Shop	3000	1981	Gasoline	7/24/89	12/15/92	12/22/94		11/2004		12/31/2006
**16	D. Marcotte	Woods-Tractor Shop	500	1981	Used Oil	7/24/89	TANK REMOVED 11/18/92 PER STATE OF NH					
**17	D. Marcotte	Woods-Tractor Shop	500	1981	Used Oil	7/24/89	TANK REMOVED 11/18/92 PER STATE OF NH					
**G1	Groveton	Riverside Trucking	10000	1979	Diesel	7/24/89	TANK REMOVED 7/21/92 PER STATE OF NH					
**G2	Groveton	Riverside Trucking	10000	1979	Diesel	7/24/89	TANK REMOVED 7/21/92 PER STATE OF NH					

** HAVE BEEN REMOVED-FOUND ON FORM ONLY AS INFORMATION

USTTOT3:UST1

Pressure Test* & Replacement Dates of Underground Storage Tanks

Tank #	Contact	Location	Size (Gal)	Date Installed	Type of Liquid	Actual Test Date	Actual Test Date	Test By	Actual Test Date	Test By	Actual Test Date	Replace Tank By
1	J. Marshall	Cascade WMTF	4000	1975	# 2 oil	7/14/88	LT	12/31/93				12/31/2000
11	D. Mercier	Sawmill Hydro	2000	1980	Kerosene	8/15/89	LT	12/31/93				12/31/2005
14	D. Marcotte	Woods-Tractor Shop	3000	1981	Diesel	7/24/89	12/15/92	12/31/93				12/31/2006
15	D. Marcotte	Woods-Tractor Shop	3000	1981	Gasoline	7/24/89	12/15/92	12/31/93				12/31/2006

UST93:UST1



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

MICROFILMED

July 9, 1990

Mr. Lynn A. Woodard
Oil Compliance Section
Groundwater Protection Bureau
Department of Environmental Services
6 Hazen Drive
Concord, NH 03302-0095

Dear Mr. Woodard:

On June 4, 1990 one 275 gallon gasoline UST (Tank #10) and one 275 gallon diesel aboveground tank were removed. Both tanks were in relatively good shape and the tank walls appeared to be intact. Bob Delisle from the Berlin City Health Department also inspected these tanks. There was some evidence of contamination in the pit where the gasoline tank had been setting. This is believed to be due to overfilling and spillage in that area. Soil and water samples were taken from around both tanks and sent away for analysis. The results are enclosed with this letter. Also enclosed are maps which show the location of the tanks and the sample points.


As there are signs of some contamination, we would like to have one of your people come here and survey the site with us so that we may come to a mutual agreement regarding cleanup. Please contact me if this is an acceptable course of action for you. I can be reached at 752-4600 ext. 2363. Thank you for your time.

Sincerely,

Jeffrey D. O'Hearn
Environmental Engineer

cc. Bob Delisle - Berlin Health
Dept.

State 1: A1




275 gal. Aboveground Tank

Diesel

AG1-Surface Sand below Tank

AG3-Sand 1 foot down



UST6

275 gal. UST


Gasoline

UST3-Dirt Wall 3 feet down

UST5-Ground water and sand
5 feet down

UST6-Surface Sand Sample

MICROFILMED



JAMES RIVER CORPORATION

MICROFILMED

INTEROFFICE CORRESPONDENCE

DATE July 3, 1990
TO Jeff O'Hearn - Berlin
FROM Ray Hanson - CES/Camas
SUBJECT Job 900332. Soil Samples for BTEX, TPH, & Volatiles.

Five soil samples were received on June 7, 1990. Four other bottles were received broken in transit. The results for BTEX and TPH are given in Table 1. We did not have freon free from nitromethane, so we conducted gravimetric analysis for TPH rather than EPA method 418.1 using infrared spectrophotometry. The volatile compounds found in sample UST5 and its liquid phase are reported in Table 2. If you have further questions please call me at (206) 834-8320.

Ray L. Hanson

RAY HANSON/dr
CES/Camas

cc: Dwight Easty - CES/Camas
Earl Hanson - Richmond
Jon Wilkinson - Berlin

Table 2
Volatile Components in Sample UST5

<u>Compounds</u>	<u>Solid Phase ($\mu\text{g/g}$)</u>	<u>Liquid Phase ($\mu\text{g/l}$)</u>
Acetone	87.0	2400
Carbon Disulfide	0.010	ND<100
Methyl Ethylketone	193.	ND<100
Chlorobenzene	1.4	ND<100

Table 1

Samples:	<u>AG1</u>	<u>AG3</u>	<u>UST3</u>	<u>UST5</u>	<u>UST6</u>	<u>UST5 Liquid Phase</u>
% Solids:	92.2	86.3	84.6	68.7	93.7	
TPH*(mg/g)	5.60	6.07	0.104	0.160	None	17.8 mg/L
Benzene ($\mu\text{g/g}$)	2.6	1.5	1.04	20.	0.48	5900 $\mu\text{g/L}$
Toluene ($\mu\text{g/g}$)	2.9	1.5	2.8	121.	0.44	15,000 $\mu\text{g/L}$
Ethylbenzene ($\mu\text{g/g}$)	6.4	0.50	0.27	24.	0.15	2300 $\mu\text{g/L}$
m-xylene ($\mu\text{g/g}$)	0.36	0.28	1.6	31.	0.18	7900 $\mu\text{g/L}$
o&p-xylene ($\mu\text{g/g}$)	0.50	0.89	1.5	25.	0.23	6700 $\mu\text{g/L}$

* Total petroleum hydrocarbon by freon extraction, silica gel cleanup of polar residues, oil, and grease. Residue weighed following evaporation of the freon.



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

October 13, 1992

Mr. Thomas Beaulieu
Groundwater Protection Bureau
NH Department of Environmental Services
6 Hazen Drive
Concord, NH 03302-0095

Dear Mr. Beaulieu:

In accordance with Env-Ws 411.18 (c) Permanent Closure we would like to inform you of our intent to remove the following Underground Storage Tanks during the week of November 16, 1992. We intend to remove a minimum of three tanks with the possibility of a fourth. These tanks include:

Tank #	Tank Contents	Tank Volume	Tank Location
5	#2 Fuel Oil	1000 gallons	Service Garage
16	Used Oil	500 gallons	Tractor Shop
17	Used Oil	500 gallons	Tractor Shop
and possibly 8	Used Oil	500 gallons	Service Garage

If there are any questions or concerns please contact me at (603) 752-4600 ext. 2363.

Sincerely,

Jeffrey O'Hearn
Environmental Engineer

ustrem1:ust1

cc: R. Danforth
J. Kusche
D. Marcott

Town Berlin Date of Closure 7/20/93
corrip

Initial V

New Hampshire Department of Environmental Services (603) 271-3644

TANK CLOSURE REPORT FORM

Telephone Message

Name Jeff O'Hearn
Street 650 Main St
City Berlin

Initial TO
Date: 6/28/93
Telephone: 342-2363
Fax # 342-2370

2. Facility Registration Number: 0-112765

Name James River Corp. Street 650 Main St
City Berlin

3. Owner Name

Name James River Corp City Berlin
Street 650 main st State NH Zip 03570 Telephone 603 342-2363

4. Tank Removal Information

*** Indicate suspected leakers. ***

Tank # <u>12</u> Size <u>1000</u> Product <u>GAS</u> will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	Tank # <u>13</u> Size <u>1000</u> Product <u>GAS</u> will tank be replaced? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Tank # <u>9</u> Size <u>4000</u> Product <u>GAS #28</u> will tank be replaced? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	Tank # <u> </u> Size <u> </u> Product <u> </u> will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>	Tank # <u> </u> Size <u> </u> Product <u> </u> will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>
---	---	--	---	---

5. Consultant unk None JR rep Jeff O'Hearn

Local Fire Dept. Notified unk Yes

7. Inspector Jeff O'Hearn

Date 7/20/93

8. Field Screening Methods (tank and piping):

HNU Photoionizer model PI 101 10.2 eV probe
#12 = 10.2 background 1.6
#13 vol = 6.0

In Tank 12 - ND
13 - ND

9. Sample Information

tank # <u>12</u> Soil <input type="checkbox"/> Water <input checked="" type="checkbox"/> <u>None</u>	tank # <u>13</u> Soil <input type="checkbox"/> Water <input checked="" type="checkbox"/> <u>None</u>	tank # <u>9</u> Soil <input type="checkbox"/> Water <input checked="" type="checkbox"/>	tank # <u> </u> Soil <input type="checkbox"/> Water <input type="checkbox"/>	tank # <u> </u> Soil <input type="checkbox"/> Water <input type="checkbox"/>
---	---	--	--	--

Taken By: Jeff O'Hearn

10. Tank Condition:

tank # <u>12</u> Rust but sturdy No holes detected	tank # <u>13</u> Rust but sturdy No holes detected	tank # <u>9</u> Bungs missing Excellent condition	tank # <u> </u>	tank # <u> </u>
---	---	--	------------------------	------------------------

11. Indicate tank and sample locations by sketching on back of this report.

12. Include photographs of the excavation and tank(s) condition if available.


13. Estimated cubic yards of stock piled contaminated soil: 4 cubic yards

14. Verification

I have inspected the site of the removed tank(s), including the entire excavation area. I am knowledgeable in field observation techniques to determine regulated substance contamination in soils and groundwater. There is no evidence of soil or groundwater contamination at the site. I have also inspected the excavated tank(s) and found no evidence of leakage.

Name: _____ Signature: _____ Date: _____


Lakeside Camp



① & ② composited into sample for tank #12


③ & ④ composited into sample for tank #13

Burgess WWTP



① ② ③ ④ ⑤ - composited into one sample
 Vac sample taken of groundwater.

Groveton



- ① → ⑧ composited into one sample for G1
⑨ → ⑬ composited into one sample for G2.
⑭ water sample taken for VOC testing.



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

January 18, 1993

Mr. Thomas Beaulieu
Groundwater Protection Bureau
NH Department of Environmental Services
6 Hazen Drive
Concord, NH 03302-0095

RE: UST Removal on November, 18, 1992

Dear Mr. Beaulieu:

Enclosed please find a written report regarding the permanent closure of four underground storage tanks from our facility on November 18, 1992. The tanks were removed by James River personnel and witnessed by Rick Treese from your Division. Analytical data is included of the soil and groundwater samples which were taken on the day of removal. Pictures of the tanks and pits have also been included.

If there is any other information that you require please contact me at (603) 752-4600 ext. 2363.

Sincerely,

Jeff O'Hearn
Environmental Engineer

ustrem92:ust1.jdo

cc: R. Danforth

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Service Garage
650 Main St. Berlin, NH 03570

Tank#: 8
Tank Volume: 500 gallons
Tank Contents: Waste Oil
Tank Location: Tank located beneath parking lot at Service Garage
Removal Date: November 18, 1992

Visual Inspection:

Ground water present in pit when tank was removed. Oil film on surface of water. A few small holes were detected in the tank. Pictures were taken of pit and tank and are included with the report.

Olfactory Inspection:

VOC headspace analysis	0.5 ppm	HNU PI101 10.2 eV PID
VOC background	0.4 ppm	

Removal Actions:

Oil absorbent pads were added to the surface of the water to remove oil. Two grab samples of soil were taken from the walls of the pit at approximately 3 feet deep in locations indicated by State of NH representative on site (Rick Treese). These samples were then composited and packaged for shipping. One sample of the liquid was taken for VOC analysis once oil was removed (Method 624 or 8240).

Laboratory Results:

% Solids	87.6
TPH	6.4 ppm dry basis
BTEX	ND<1 ppm for all compounds
TCLP	Data attached

VOC of water sample: Attached

Disposal:

Contaminated Soil was sent to Mt. Carberry Landfill for disposal following all permit conditions. Tanks were inspected to ensure cleanliness and were then crushed and taken to the James River General Debris Landfill.

ustrem92:ust1.jdo

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Service Garage
650 Main St. Berlin, NH 03570

Tank#: 5
Tank Volume: 1000 gallons
Tank Contents: #2 Heating Oil
Tank Location: Tank located beneath parking lot at Service Garage.
Removal Date: November 18, 1992

Visual Inspection:

Small amount of groundwater detected at bottom of pit. No visible contamination of water readily apparent. Tank appeared to be in good condition. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	0.7 ppm	HNU PI101 10.2 eV PID
VOC background	0.4 ppm	

Removal Actions:

Two grab samples of soil were taken from the walls of the pit at each end of the tank at approximately 4 feet deep in locations indicated by State of NH representative on site (Rick Treese). These samples were then composited and packaged for shipping.

Laboratory Results:

% Solids	92.4
TPH	260 ppm dry basis
TPH (dup)	290 ppm dry basis
BTEX	ND<1 ppm for all compounds
TCLP	Data attached

Disposal:

Contaminated Soil was sent to Mt. Carberry Landfill for disposal following all permit conditions. Tanks were inspected to ensure cleanliness and were then crushed and taken to the James River General Debris Landfill.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

ustrem92:ust1.jdo

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Tractor Shop
650 Main St. Berlin, NH 03570

Tank#: 16
Tank Volume: 500 gallons
Tank Contents: Waste Oil
Tank Location: Tank located beneath parking lot at Tractor Shop
Removal Date: November 18, 1992

Visual Inspection:

No groundwater was detected in the pit. Tank appeared to be in good condition. Some visible contamination was present on top of tank. This was traced to a union on a diesel line that ran over the tank. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	0.4 ppm	HNU PI101 10.2 eV PID
VOC background	0.4 ppm	

Removal Actions:

Two grab samples of soil were taken from the walls of the pit at each end of the tank at approximately 4 feet deep in locations indicated by State of NH representative on site (Rick Treese). These samples were then composited and packaged for shipping.

Laboratory Results:

% Solids	92.9
TPH	4800 ppm dry basis
BTEX	ND<1 ppm for all compounds
TCLP	Data attached

Disposal:

Contaminated Soil was sent to Mt. Carberry Landfill for disposal following all permit conditions. Tanks were inspected to ensure cleanliness and were then crushed and taken to the James River General Debris Landfill.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

ustrem92:ust1.jdo

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Tractor Shop
650 Main St. Berlin, NH 03570

Tank#: 17
Tank Volume: 500 gallons
Tank Contents: Waste Oil
Tank Location: Tank located beneath parking lot at Tractor Shop
Removal Date: November 18, 1992

Visual Inspection:

No groundwater was detected in the pit. Tank appeared to be in good condition. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	0.4 ppm	HNU PI101 10.2 eV PID
VOC background	0.4 ppm	

Removal Actions:

Two grab samples of soil were taken from the walls of the pit at each end of the tank at approximately 4 feet deep in locations indicated by State of NH representative on site (Rick Treese). These samples were then composited and packaged for shipping.

Laboratory Results:

% Solids	91.6
TPH	570 ppm dry basis
BTEX	ND<1 ppm for all compounds
TCLP	Data attached

Disposal:

Contaminated Soil was sent to Mt. Carberry Landfill for disposal following all permit conditions. Tanks were inspected to ensure cleanliness and were then crushed and taken to the James River General Debris Landfill.

ustrem92:ust1.jdo


Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

ustrem92:ust1.jdo



JAMES RIVER CORPORATION

INTEROFFICE CORRESPONDENCE

DATE January 5, 1993
TO Jeff O'Hearn - Berlin
FROM Dwight Easty - CES/Camas
SUBJECT Lab Reference No. 920596 - Analysis of Water and Soil Samples

Results of analysis of the UST soil and water samples collected 11/18/92 are shown in the enclosed tables. These data confirm the results reported by telephone on 1/4/93.

Please call if you have questions about results.

Dwight Easty

DWIGHT EASTY/gh

cc: Earl Hanson - Richmond

Attachments

TABLE 1. EPA VOLATILE PRIORITY POLLUTANT ANALYSIS

Source: Berlin
 JRESL Reference: 920596-8
 Sample: #8W
 Method: EPA Method 624, Purge-and-Trap GC/MS

COMPOUND	Concentration in ug/L (ppb)		
	MDL*	Lab Blank	8W
Chloromethane	5	ND	ND
Bromomethane	1	ND	ND
Vinyl chloride	1	ND	ND
Chloroethane	1	ND	ND
Dichloromethane	1	0.6	1
Trichlorofluoromethane	1	ND	ND
1,1-Dichloroethylene	1	ND	ND
1,1-Dichloroethane	1	ND	2
Z-1,2-Dichloroethylene	1	ND	ND
Chloroform	1	ND	ND
1,2-Dichloroethane	1	ND	ND
1,1,1-Trichloroethane	1	ND	97
Carbon tetrachloride	1	ND	ND
Bromodichloromethane	1	ND	ND
1,2-Dichloropropane	2	ND	ND
E-1,3-Dichloropropylene	1	ND	ND
Trichloroethylene	1	ND	ND
Benzene	1	0.7	9
Dibromochloromethane	1	ND	ND
Z-1,3-Dichloropropylene	1	ND	ND
1,1,2-Trichloroethane	1	ND	ND
2-Chloroethylvinyl ether	5	ND	ND
Bromoform	1	ND	ND
Tetrachloroethylene	1	0.8	6
1,1,2,2-Tetrachloroethane	1	ND	ND
Toluene	1	ND	46
Chlorobenzene	1	ND	ND
Ethylbenzene	1	ND	4
Xylenes	1	ND	52
Dichlorobenzene	1	ND	ND

* Minimum detection limit

ND means not detected.

Lower values reported where absence of interference permits.

Table 2
Analysis of Soils: TPH and BTEX
Lab Reference No: 920596

<u>Sample</u>	<u>Solids, %</u>	<u>TPH¹ µg/g, dry basis</u>	<u>BTEX³, µg/g, dry basis</u>
# 8	87.6	6.4	ND <1 ⁴
# 16	92.9	4800	ND <1
# 17	91.6	570	ND <1
# 5	92.4	260, 290 ²	ND <1

ND means not detected.

¹ Total petroleum hydrocarbons

² Duplicate determinations. Recovery of 5531 µg/g spike added to #5: 96%.

³ Benzene, toluene, ethylbenzene, xylene.

⁴ Detection limit: 1 µg/g of each compound.

Table 3
Determination of Metals in TCLP Extract
Lab Reference No: 920596

Element	Concentration in mg/L					Spike Recovery, % ¹
	Regulatory Level	Detection Limit	#8	#16	#17	
Arsenic	5	0.06	ND	ND	ND	98
Barium	100	0.05	0.14	0.45	0.47	86
Cadmium	1	0.005	ND	ND	ND	103
Chromium	5	0.006	0.007	ND	ND	86
Lead	5	0.06	ND	ND	ND	102
Mercury	0.2	0.005	ND	ND	ND	109
Selenium	1	0.03	ND	ND	ND	99
Silver	5	0.05	ND	ND	ND	NA

ND means not detected

¹ Spike added to TCLP extract of #16: mercury, 0.00625 mg/L;
other elements, 0.25 mg/L; silver was not added (NA).

Table 4
Determination of Volatiles in TCLP Extract
Lab Reference No. 920596

	<u>Concentration in mg/L</u>				
	<u>Regulatory Level</u>	<u>Detection Limit</u>	<u>#8</u>	<u>#16</u>	<u>#17</u>
Benzene	0.50	0.010	ND	ND	ND
Carbon Tetrachloride	0.50	0.010	ND	ND	ND
Chlorobenzene	100	0.010	ND	ND	ND
Chloroform	6.0	0.010	ND	ND	ND
1,2-Dichloroethane	0.50	0.010	ND	ND	ND
1,1-Dichloroethylene	0.70	0.010	ND	ND	ND
Methyl Ethyl Ketone	200	0.010	ND	ND	ND
Tetrachloroethylene	0.70	0.010	ND	ND	ND
Trichloroethylene	0.50	0.010	ND	ND	ND
Vinyl Chloride	0.20	0.010	ND	ND	ND

means not detected

Table 5

Determination of Semivolatiles in TCLP Extract

Lab Reference No. 920596

<u>Semivolatile Organics</u>	<u>Regulatory Level (mg/L)</u>	<u>Detection Limit, mg/L</u>	<u>Concentration in TCLP Extract, mg/L</u>		
			<u>#8</u>	<u>#16</u>	<u>#17</u>
Chlordane	0.03	--	NR	NR	NR
o-Cresol	200.0	0.0002	ND	ND	ND
m-Cresol	200.0	0.0002	ND	ND	ND
p-Cresol	200.0	0.0002	ND	ND	ND
Total Cresol	200.0	0.0002	ND	ND	ND
2,4-D	10.0	--	NR	NR	NR
1,4-Dichlorobenzene	7.5	0.0002	ND	ND	ND
2,4-Dinitrotoluene	0.13	0.0005	ND	ND	ND
Endrin	0.02	--	NR	NR	NR
Heptachlor (and its epoxide)	0.008	--	NR	NR	NR
Hexachlorobenzene	0.13	0.0002	ND	ND	ND
Hexachloro-1,3-butadiene	0.5	0.0002	ND	ND	ND
Hexachlorethane	3.0	0.0002	ND	ND	ND
Lindane	0.4	--	NR	NR	NR
Methoxychlor	10.0	--	NR	NR	NR
Nitrobenzene	2.0	0.0008	ND	ND	ND
Pentachlorophenol	100	0.010	ND	ND	ND
Pyridine	5.0	1	ND	ND	ND
Toxaphene	0.5	--	NR	NR	NR
2,4,5-Trichlorophenol	400.0	0.0002	ND	ND	ND
2,4,6-Trichlorophenol	2.0	0.0002	ND	ND	ND
2,4,5-TP (Silvex)	1.0	--	NR	NR	NR

Pesticides and herbicides were not requested (NR).

ND means not detected.

Methods:

TPH	-	Freon extraction and infrared analysis. EPA Method 418.1
VOC's and BTEX	-	EPA Method 624/8240
TCLP Extraction	-	EPA Method 1311
Mercury	-	EPA Method 245.1
Other Metals	-	EPA Method 6010A
Pyridine	-	GC/FID
Other semivolatiles	-	EPA Method 625/8270

Analysts:

R. R. Claeys
T. A. Linn
D. L. Wong
V. Claxton
K. Haunreiter



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

F/U 7/17/93

JOH

June 22, 1993

Mr. Thomas Beaulieu
Groundwater Protection Bureau
NH Department of Environmental Services
6 Hazen Drive
Concord, NH 03302-0095

Dear Mr. Beaulieu:

In accordance with Env-Ws 411.18 (c) Permanent Closure we would like to inform you of our intent to remove the following Underground Storage Tanks during the week of July 19, 1993. We intend to remove five tanks from three different locations. These tanks include:

Tank #	Tank Contents	Tank Volume	Tank Location
12	Unleaded Gasoline	1000 gallons	Cambridge Camp
13	Unleaded Gasoline	1000 gallons	Cambridge Camp
9	#2 Fuel Oil	4000 gallons	Burgess WWTP
G1	Diesel Fuel	10000 gallons	Groveton
G2	Diesel Fuel	10000 gallons	Groveton

If there are any questions or concerns please contact me at (603) 342-2363.

Sincerely,

Jeffrey O'Hearn
Environmental Project Engineer

ustrem2:ust1

cc: R. Danforth
B. Wyman
D. Marcotte

TANK CLOSURE REPORT FORM

Telephone Message

Name Jeff O'Hearn
 Street 650 Main St
 City Berlin

Initial TP
 Date: 6/28/93
 Telephone: 342-2363
 Fax # 342-2370

2. Facility Registration Number: 0-112765

Name James River Corp. Street 650 Main St
 City Berlin

3. Owner Name

Name James River Corp City Berlin
 Street 650 Main St State NH Zip 03570 Telephone 603 342-2363

4. Tank Removal Information

*** Indicate suspected leakers. ***

Tank # <u>12</u>	Tank # <u>13</u>	Tank # <u>9</u>	Tank # _____	Tank # _____
Size <u>1000</u>	Size <u>1000</u>	Size <u>4000</u>	Size _____	Size _____
Product <u>GAS</u>	Product <u>GAS</u>	Product <u>GAS</u> #2 Fuel	Product _____	Product _____
will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>

5. Consultant Unk None JK rep. Jeff O'Hearn6. Local Fire Dept. Notified Unk Yes7. Inspector Jeff O'HearnDate 7/20/93

8. Field Screening Methods (tank and piping):

HNU Photoionizer model PI 101 10.2 eV probe
 #12 = 10.2 background 1.6
 #13 = 6.0

In Tank 12 - ND
 13 - NO

9. Sample Information

tank # <u>12</u>	tank # <u>13</u>	tank # <u>9</u>	tank # _____	tank # _____
Soil / Water <u>None</u>	Soil / Water <u>None</u>	Soil / Water <u>✓</u>	Soil / Water _____	Soil / Water _____

Taken By: Jeff O'Hearn

10. Tank Condition:

tank # <u>12</u> Rust but sturdy No holes detected	tank # <u>13</u> Rust but sturdy No holes detected	tank # <u>9</u> Bungs missing Excellent condition	tank # _____	tank # _____
---	---	--	--------------	--------------

11. Indicate tank and sample locations by sketching on back of this report.

12. Include photographs of the excavation and tank(s) condition if available.


13. Estimated cubic yards of stock piled contaminated soil: 4 cubic yards

14. Verification

I have inspected the site of the removed tank(s), including the entire excavation area. I am knowledgeable in field observation techniques to determine regulated substance contamination in soils and groundwater. There is no evidence of soil or groundwater contamination at the site. I have also inspected the excavated tank(s) and found no evidence of leakage.

Name: _____ Signature: _____ Date: _____


Lakeside Camp



① & ② composited into sample for tank #12

③ & ④ composited into sample for tank #13

Burgess WWTP



① ② ③ ④ ⑤ - composited into one sample

VOC sample taken of groundwater.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Lakeside Camp - Cambridge NH
650 Main St. Berlin, NH 03570

Tank#: 12
Tank Volume: 1000 gallons
Contents: Unleaded Gasoline
Removal Date: July 20, 1993

Visual Inspection:

No groundwater was present in the pit when the tank was removed. There was some minimal soil contamination evident in the area of the piping to the tank. This contamination was believed to have been caused by residual fuel in the lines that spilled when the lines were removed. The tank was in excellent condition and no holes were detected. The piping and fittings also seemed to be free of leaks. Pictures were taken of pit and tank and are included with the report.

Olfactory Inspection:

VOC headspace analysis	10.2 ppm	HNU PI101 10.2 eV PID
VOC background	1.6 ppm	

Removal Actions:

Two grab samples of soil were taken from the walls of the pit at approximately 4 feet deep in locations at each end of the tank. These samples were then composited and packaged for shipping.

Laboratory Results:

% Solids	94.0
TPH	58 ppm dry basis
BTEX	ND<0.2 ppm for all compounds

Disposal:

The pits were filled in with fill following the removal of the tanks and lines. Tanks were inspected to ensure cleanliness and are stored at the James River Service Garage awaiting disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

ustrem93:ust1.jdo

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Burgess Wastewater Treatment Plant
650 Main St. Berlin, NH 03570

Tank#: 9
Tank Volume: 4000 gallons
Tank Contents: #2 Heating Oil
Tank Location: Tank located at rear of building.
Removal Date: July 20, 1993

Visual Inspection:

Small amount of groundwater detected at bottom of pit. There was a light sheen on the surface of the water and absorbent pads were placed in the hole to absorb this. Contamination of the soil at the building end of the tank was visible. After thorough inspection of the tank no leaks were detected and no rust was present. It appeared that one of the bungs on the top of the tank was missing in the general location where the most contamination was present in the pit. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	58 ppm	HNU PI101 10.2 eV PID
VOC background	4.0 ppm	

Removal Actions:

One grab sample of soil were taken from each end of the tank and three grab samples were collected along the walls of the tank at approximately 4 feet deep. The samples were composited into one sample. One sample of the groundwater in the pit was also collected. The samples were then packaged for shipping.

Laboratory Results:

% Solids	85.8
TPH	220 ppm dry basis
TPH (dup)	200 ppm dry basis
BTEX	ND<0.2 ppm for all compounds

VOC on Water Sample: See attached

Disposal:

Jack Schwaziack of the State Groundwater Protection Division was contacted when the soil contamination was detected.

ustrem93:ust1.jdo

Following his instructions, we removed as much of the contaminated soil as was possible and transported this to MT. Carberry Landfill for storage. The pit was then filled in with clean fill. Tanks were inspected to ensure cleanliness and are stored at the Service Garage awaiting disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

TABLE 1A. VOLATILES IN GROUNDWATER

Source: Berlin
 JRESL Reference: 930381
 Sample: Groundwater Sample 9W
 Method: EPA Method 624, Purge-and-Trap GC/MS

COMPOUND	CONCENTRATION in ug/L (ppb)		
	MDL*	Lab Blank	9W 7/20/93
Chloromethane	10	ND	ND
Bromomethane	10	ND	ND
Vinyl chloride	10	ND	ND
Chloroethane	10	ND	ND
Dichloromethane	2	ND	ND
Trichlorofluoromethane	2	ND	ND
1,1-Dichloroethene	2	ND	ND
1,1-Dichloroethane	2	ND	ND
trans-1,2-Dichloroethene	2	ND	ND
Chloroform	2	ND	ND
1,2-Dichloroethane	2	ND	ND
1,1,1-Trichloroethane	2	ND	ND
Carbon tetrachloride	2	ND	ND
Bromodichloromethane	2	ND	ND
1,2-Dichloropropane	4	ND	ND
cis-1,3-Dichloropropene	2	ND	ND
Trichloroethene	2	ND	ND
Benzene	2	ND	ND
Dibromochloromethane	2	ND	ND
trans-1,3-Dichloropropene	2	ND	ND
1,1,2-Trichloroethane	2	ND	ND
2-Chloroethylvinyl ether	10	ND	ND
Bromoform	2	ND	ND
Tetrachloroethene	2	ND	ND
1,1,2,2-Tetrachloroethane	2	ND	ND
Toluene	2	ND	ND
Chlorobenzene	2	ND	ND
Ethylbenzene	2	ND	ND
Xylenes	2	ND	43
1,3-Dichlorobenzene	2	ND	ND
1,2- & 1,4-Dichlorobenzene	2	ND	ND

*Minimum Detection Limit
 ND means not detected




State of New Hampshire
DEPARTMENT OF ENVIRONMENTAL SERVICES

6 Hazen Drive, P.O. Box 95, Concord, NH 03302-0095

603-271-3503 FAX 603-271-2867

TDD Access: Relay NH 1-800-735-2964



March 7, 1994

James River Corporation
650 Main Street
Berlin, New Hampshire 03570
Attn: Jeffrey O'Hearn

RE: BERLIN, JAMES RIVER, TANK CLOSURE REPORT RECEIVED AUGUST 30, 1993
(UST #0-112765)

Dear Mr. O'Hearn:

The New Hampshire Department of Environmental Services (DES) has reviewed the Tank Closure Report for the 1,000 gallon gasoline tank and a 4,000 gallon gasoline tank submitted concerning the above referenced facility and we have the following comments:

1. Based upon the information provided, it appears that a discharge of petroleum that will ultimately seep into surface water or groundwater of the State has not occurred. Therefore, DES will not require additional investigation or remedial measures at this time.
2. The owner(s) of this facility must meet the goals of N.H. Admin. Rules Env-Ws 410 "Groundwater Protection Rules," that is, groundwater at the site must continue to meet drinking water quality standards.
3. DES reserves the right, under N.H. Admin. Rules Env-Ws 410 "Groundwater Protection Rules" and N.H. Admin. Rules Env-Ws 412 "Rules for Reporting and Remediation of Oil Discharges," to require additional hydrogeological investigations and/or remedial measures if further information indicating the need for such work is received.

If you have questions, contact me at the Water Supply & Pollution Control Division at (603) 271-3644.

Sincerely,

Thomas R. Beaulieu
Groundwater Protection Bureau

TRB/emw:97/8155
cc: File

AIR RESOURCES DIV.
64 No. Main Street
Caller Box 2033
Concord, N.H. 03302-2033
Tel. 603-271-1370
Fax 603-271-1381

WASTE MANAGEMENT DIV.
6 Hazen Drive
Concord, N.H. 03301
Tel. 603-271-2900
Fax 603-271-2456

WATER RESOURCES DIV.
64 No. Main Street
P.O. Box 2008
Concord, N.H. 03302-2008
Tel. 603-271-3406
Fax 603-271-6588

WATER SUPPLY & POLLUTION CONTROL DIV.
P.O. Box 95
Concord, N.H. 03302-0095
Tel. 603-271-3503
Fax 603-271-2181



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

March 11, 1994

Mr. Thomas R. Beaulieu
N.H. Department of Environmental Services
Groundwater Protection Bureau
6 Hazen Drive, P.O. Box 95
Concord, NH 03302-0095

Dear Mr. Beaulieu:

This letter is in response to your letter of March 7, 1994 regarding the tank closure report which we submitted on August 30, 1993. I would like question a discrepancy which I noted in your response. Your letter references one 1,000 gallon gasoline tank and one 4,000 gallon gasoline tank that were closed. The tanks that were removed were actually two 1,000 gallon gasoline tanks and one 4,000 gallon #2 Fuel Oil tank. I would appreciate it if you would look into this and let me know of your results.

If you have any questions please contact me at (603) 342-2363.

Sincerely,

Jeffrey O'Hearn
Environmental Project Engineer

ust_clsr_0793_nhresp1:vwf.hzw_jdo

cc: R. Danforth

No response from State of NH

comp

Initial ✓

New Hampshire Department of Environmental Services (603) 271-3644

TANK CLOSURE REPORT FORM

Telephone Message

Name Jeffrey O'Hearn / James River
 Street 650 Main St
 City Berlin NH

Initial TB
 Date: 6/28/93
 Telephone: 342-2363
 Fax # _____

2. Facility Registration Number: 0-111933

Name James River Corp (Riverside) Street Mechanic St
 City Northumberland

3. Owner Name

Name _____ City _____
 Street _____ State _____ Zip _____ Telephone _____

4. Tank Removal Information

*** Indicate suspected leakers. ***

Tank #	Tank #	Tank #	Tank #	Tank #
<u>G1</u>	<u>G2</u>	_____	_____	_____
Size <u>10 000</u>	Size <u>10 000</u>	Size _____	Size _____	Size _____
Product <u>DSC</u>	Product <u>DSC</u>	Product _____	Product _____	Product _____
will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>	will tank be replaced? Yes <input type="checkbox"/> No <input type="checkbox"/>

5. Consultant None JK contact Jeff O'Hearn6. Local Fire Dept. Notified None Yes7. Inspector Jeff O'HearnDate 7/21/93

3. Field Screening Methods (tank and piping):

VOC testing mini photo ionizer PIED 10000 probe
G1 16 ppm background 3 ppm
G2 7.6 ppm

3. Sample Information

tank #	tank #	tank #	tank #	tank #
<u>G1</u>	<u>G2</u>	_____	_____	_____
Soil <input checked="" type="checkbox"/> Water <input checked="" type="checkbox"/>	Soil <input checked="" type="checkbox"/> Water <input checked="" type="checkbox"/>	Soil <input type="checkbox"/> Water <input type="checkbox"/>	Soil <input type="checkbox"/> Water <input type="checkbox"/>	Soil <input type="checkbox"/> Water <input type="checkbox"/>

Taken By: _____

0. Tank Condition:

tank #	tank #	tank #	tank #	tank #
<u>excellent</u>	<u>excellent</u>	_____	_____	_____

1. Indicate tank and sample locations by sketching on back of this report.


2. Include photographs of the excavation and tank(s) condition if available.

3. Estimated cubic yards of stock piled contaminated soil: 160 cubic yards

4. Verification

I have inspected the site of the removed tank(s), including the entire excavation area. I am knowledgeable in field verification techniques to determine regulated substance contamination in soils and groundwater. There is no evidence of soil or groundwater contamination at the site. I have also inspected the excavated tank(s) and found no evidence of leakage.

Grove:ton



- ① → ⑧ composited into one sample for G1
⑨ → ⑬ composited into one sample for G2.
⑭ water sample taken for VOC testing.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Groveton Facility
650 Main St. Berlin, NH 03570

Tank#: G1
Tank Volume: 10000 gallons
Tank Contents: Diesel Fuel
Tank Location: Tank located beneath parking lot
Removal Date: July, 21, 1993

Visual Inspection:

Some groundwater was detected in the pit with a slight sheen of oil on the surface in a couple of the puddles. The tank was in excellent condition. Some contamination was detected in the area of the tank fill pipe possible due to overfilling in the past. The pipes themselves were also in good condition. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	16.0 ppm	HNU PI101 10.2 eV PID
VOC background	3.0 ppm	

Removal Actions:

A grab sample of soil was taken from each end of the tank and 6 samples were taken along the length at approximately 4 feet deep in locations. These samples were then composited into one sample. A groundwater sample was also taken. The samples were then packaged for shipping.

Laboratory Results:

% Solids	91.4
TPH	680 ppm dry basis
BTEX	ND<0.2 ppm for all compounds

VOC on water sample: See attached

Disposal:

Contaminated Soil was sent to Mt. Carberry Landfill for disposal following all permit conditions. Rick Berry from the State Groundwater Protection Division was contacted and informed of the soil contamination that was present. The pit

ustrem93:ust1.jdo

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Lakeside Camp - Cambridge NH
650 Main St. Berlin, NH 03570

Tank#: 13
Tank Volume: 1000 gallons
Tank Contents: Unleaded Gasoline
Removal Date: July 20, 1993

Visual Inspection:

No groundwater was present in the pit when the tank was removed. There was no contamination evident in the area of this tank. The tank was in excellent condition and no holes were detected. Pictures were taken of pit and tank and are included with the report.

Olfactory Inspection:

VOC headspace analysis	6.0 ppm	HNU PI101 10.2 eV PID
VOC background	1.6 ppm	

Removal Actions:

Two grab samples of soil were taken from the walls of the pit at approximately 4 feet deep in locations at each end of the tank. These samples were then composited and packaged for shipping.

Laboratory Results:

% Solids	89.1
TPH	44 ppm dry basis
BTEX	ND<0.2 ppm for all compounds

Disposal:

Tanks were inspected to ensure cleanliness and are currently stored at the James River Service Garage awaiting disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from Spills/Releases of Virgin Petroleum Products 9/91 and Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

ustrem93:ust1.jdo

was then filled in with new clean fill. The tanks were inspected for cleanliness and are stored at the Service Garage awaiting disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

TABLE 1B. VOLATILES IN GROUNDWATER

Source: Berlin
 JRESL Reference: 930382
 Sample: Groundwater Sample GW
 Method: EPA Method 624, Purge-and-Trap GC/MS

COMPOUND	CONCENTRATION in ug/L (ppb)		
	MDL*	Lab Blank	GW 7/21/93
Chloromethane	10	ND	ND
Bromomethane	10	ND	ND
Vinyl chloride	10	ND	ND
Chloroethane	10	ND	ND
Dichloromethane	2	ND	ND
Trichlorofluoromethane	2	ND	ND
1,1-Dichloroethene	2	ND	ND
1,1-Dichloroethane	2	ND	ND
trans-1,2-Dichloroethene	2	ND	ND
Chloroform	2	ND	ND
1,2-Dichloroethane	2	ND	ND
1,1,1-Trichloroethane	2	ND	ND
Carbon tetrachloride	2	ND	ND
Bromodichloromethane	2	ND	ND
1,2-Dichloropropane	4	ND	ND
cis-1,3-Dichloropropene	2	ND	ND
Trichloroethene	2	ND	ND
Benzene	2	ND	ND
Dibromochloromethane	2	ND	ND
trans-1,3-Dichloropropene	2	ND	ND
1,1,2-Trichloroethane	2	ND	ND
2-Chloroethylvinyl ether	10	ND	ND
Bromoform	2	ND	ND
Tetrachloroethene	2	ND	ND
1,1,2,2-Tetrachloroethane	2	ND	ND
Toluene	2	ND	ND
Chlorobenzene	2	ND	ND
Ethylbenzene	2	ND	ND
Xylenes	2	ND	ND
1,3-Dichlorobenzene	2	ND	ND
1,2-&-1,4-Dichlorobenzene	2	ND	ND

*Minimum Detection Limit
 ND means not detected.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Groveton Facility
650 Main St. Berlin, NH 03570

Tank#: G2
Tank Volume: 10000 gallons
Tank Contents: Diesel Fuel
Tank Location: Tank located beneath parking lot
Removal Date: July, 21, 1993

Visual Inspection:

Some groundwater was detected in the pit with a slight sheen of oil on the surface in a couple of the puddles. The tank was in excellent condition. Some contamination was detected in the area of the tank fill pipe possible due to overfilling in the past. The pipes themselves were in good condition. Pictures were taken of tank and pit.

Olfactory Inspection:

VOC headspace analysis	7.6 ppm	HNU PI101 10.2 eV PID
VOC background	3.0 ppm	

Removal Actions:

A grab sample of soil was taken from each end of the tank and 6 samples were taken along the length at approximately 4 feet deep in locations. These samples were then composited into one sample for analysis. A groundwater sample (see Tank G1 inspection form) was also taken. The samples were then packaged for shipping.

Laboratory Results:

% Solids	93.0
TPH	290 ppm dry basis
BTEX	ND<0.2 ppm for all compounds

Disposal:

All removed from the pit was sent to Mt. Carberry Landfill for disposal following all permit conditions. Rick Berry from the State Groundwater Protection Division was contacted and informed of the soil contamination that was present. The pit was then filled in with new clean fill. The tanks were

ustrem93:ust1.jdo

inspected for cleanliness and are stored at the Service Garage awaiting disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines April 1991

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.



JAMES RIVER CORPORATION

INTEROFFICE CORRESPONDENCE

DATE August 23, 1993
TO Jeff O'Hearn - Berlin
FROM Dwight Easty - CES/Camas
SUBJECT Lab Reference 930381 and 930382 - Analysis of Water and Soil Samples

Results of analysis of the groundwater and soil samples collected July 20 and 21 are shown in the enclosed tables. Please note that xylene was detected in groundwater sample 9W.

Please call if you have questions about these results.

Dwight Easty

DWIGHT EASTY

C:
Earl Hanson - Richmond

Enclosures

Post-It™ brand fax transmittal memo 7671		# of pages ▶ 5
To. Tom Beaulieu	From Jeff O'Hearn	
Co. NH DES	Co. JR	
Dept.	Phone #	
Fax # 271-2181	Fax # 342-2337	

Tom Beaulieu
271-2181

TABLE 1A. VOLATILES IN GROUNDWATER

Source: Berlin
 JRESL Reference: 930381
 Sample: Groundwater Sample 9W
 Method: EPA Method 624, Purge-and-Trap GC/MS

COMPOUND	CONCENTRATION in ug/L (ppb)		
	MDL*	Lab Blank	9W 7/20/93
Chloromethane	10	ND	ND
Bromomethane	10	ND	ND
Vinyl chloride	10	ND	ND
Chloroethane	10	ND	ND
Dichloromethane	2	ND	ND
Trichlorofluoromethane	2	ND	ND
1,1-Dichloroethene	2	ND	ND
1,1-Dichloroethane	2	ND	ND
trans-1,2-Dichloroethene	2	ND	ND
Chloroform	2	ND	ND
1,2-Dichloroethane	2	ND	ND
1,1,1-Trichloroethane	2	ND	ND
Carbon tetrachloride	2	ND	ND
Bromodichloromethane	2	ND	ND
1,2-Dichloropropane	4	ND	ND
cis-1,3-Dichloropropene	2	ND	ND
Trichloroethene	2	ND	ND
Benzene	2	ND	ND
Dibromochloromethane	2	ND	ND
trans-1,3-Dichloropropene	2	ND	ND
1,1,2-Trichloroethane	2	ND	ND
2-Chloroethylvinyl ether	10	ND	ND
Bromoform	2	ND	ND
Tetrachloroethene	2	ND	ND
1,1,2,2-Tetrachloroethane	2	ND	ND
Toluene	2	ND	ND
Chlorobenzene	2	ND	ND
Ethylbenzene	2	ND	ND
Xylenes	2	ND	43
1,3-Dichlorobenzene	2	ND	ND
1,2-&-1,4-Dichlorobenzene	2	ND	ND

*Minimum Detection Limit
 ND means not detected

TABLE 1B. VOLATILES IN GROUNDWATER

Source: Berlin
 JRESL Reference: 930382
 Sample: Groundwater Sample GW
 Method: EPA Method 624, Purge-and-Trap GC/MS

COMPOUND	CONCENTRATION in ug/L (ppb)		
	MDL*	Lab Blank	GW 7/21/93
Chloromethane	10	ND	ND
Bromomethane	10	ND	ND
Vinyl chloride	10	ND	ND
Chloroethane	10	ND	ND
Dichloromethane	2	ND	ND
Trichlorofluoromethane	2	ND	ND
1,1-Dichloroethene	2	ND	ND
1,1-Dichloroethane	2	ND	ND
trans-1,2-Dichloroethene	2	ND	ND
Chloroform	2	ND	ND
1,2-Dichloroethane	2	ND	ND
1,1,1-Trichloroethane	2	ND	ND
Carbon tetrachloride	2	ND	ND
Bromodichloromethane	2	ND	ND
1,2-Dichloropropane	4	ND	ND
cis-1,3-Dichloropropene	2	ND	ND
Trichloroethene	2	ND	ND
Benzene	2	ND	ND
Dibromochloromethane	2	ND	ND
trans-1,3-Dichloropropene	2	ND	ND
1,1,2-Trichloroethane	2	ND	ND
2-Chloroethylvinyl ether	10	ND	ND
Bromoform	2	ND	ND
Tetrachloroethene	2	ND	ND
1,1,2,2-Tetrachloroethane	2	ND	ND
Toluene	2	ND	ND
Chlorobenzene	2	ND	ND
Ethylbenzene	2	ND	ND
Xylenes	2	ND	ND
1,3-Dichlorobenzene	2	ND	ND
1,2-&-1,4-Dichlorobenzene	2	ND	ND

*Minimum Detection Limit
 ND means not detected.

Table 2
Analysis of Soils: TPH and BTEX
Lab Reference 930381 and 930382

<u>Sample</u>	<u>Solids, %</u>	<u>TPH¹ ug/g, dry basis</u>	<u>BTEX³ ug/g, dry basis</u>
9	85.8	220, 200 ²	ND <0.2 ⁴
12	94.0	58	ND <0.2
13	89.1	44	ND <0.2
G1	91.4	680	ND <0.2
G2	93.0	290	ND <0.2

ND means not detected.

¹ Total petroleum hydrocarbons

² Duplicate determinations. Recovery of 460 ug/g spike added to sample 13: 80%.

³ Benzene, toluene, ethylbenzene, xylene.

⁴ Detection limit: 0.2 ug/g of each compound.

Table 3
BTEX Spike Recovery
Lab Reference 930381

	<u>Spike Recovery,¹ %</u>
Benzene	78
Toluene	80
Ethylbenzene	92
m-Xylene	95

¹ Amount of spike added to sample 13: 4 ug/g of each compound.

Methods:

VOC's and BTEX - EPA Method 624/8240
TPH - Freon extraction and infrared analysis.
EPA Method 418.1

Analysts:

V. Claxton
K. Haunreiter
R. Smith



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

August 26, 1993

Mr. Bob Delisle
Berlin Health Department
Main Street
Berlin, NH 03570

Dear Bob:

Enclosed please find a copy of the report which we have submitted to the State in regards to the removal of the underground #2 fuel tank from the Burgess Wastewater Treatment Plant. The results of the testing of the soil and groundwater from the tank site are included in the report.

If you have any questions about this information please give me a call at (603) 342-2363.

Sincerely,

Jeffrey O'Hearn
Environmental Project Engineer

cc: R. Danforth



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

August 26, 1993

Mr. Thomas Beaulieu
Groundwater Protection Bureau
NH Department of Environmental Services
6 Hazen Drive
Concord, NH 03302-0095

RE: UST Removal on July 20, 1993

Dear Mr. Beaulieu:

Enclosed please find a written report regarding the permanent closure of three underground storage tanks from our facility (O-112765) on July 20, 1993 and the permanent closure of two tanks at our former Groveton facility (O-111933) on July 21, 1993. The tanks were removed and witnessed by James River personnel. A State representative was requested but due to scheduling conflicts was unable to witness the removal. Analytical data is included of the soil and groundwater samples which were taken during the removals. Pictures of the tanks and pits have also been included.

If there is any other information that you require please contact me at (603) 342-2363.

Sincerely,

Jeff O'Hearn
Environmental Project Engineer

ustrem93:ust1

cc: R. Danforth



JAMES RIVER CORPORATION
COMMUNICATION PAPERS/N.E. GROUP
650 Main St., Berlin, NH 03570-2489 (603) 752-4600

August 27, 1993

Mr. Carl Woodbury
Waste Management Division
NH Department of Environmental Services
6 Hazen Drive
Concord, NH 03301

Dear Mr. Woodbury:

Enclosed please find the soil test results for the soil we removed from our underground tank removals at our former Groveton facility, our Lakeside logging camp in Cambridge, and our Burgess Treatment Plant. We currently have approximately 160 yd³ of soil from Groveton (sample G1 and G2) and 4 yd³ from the Treatment Plant (sample 9) stored at our Mt Carberry Landfill. We did not remove any of the soil from the Lakeside Camp (samples 12 and 13). We would like permission to dispose of this soil in Mt. Carberry Landfill.

If you have any questions or concerns please contact me at (603) 342-2363.

Sincerely,

Jeffrey O'Hearn
Environmental Project Engineer

cc: R. Danforth

Table 2

Analysis of Soils: TPH and BTEX

Lab Reference 930381 and 930382

<u>Sample</u>	<u>Solids, %</u>	<u>TPH¹ ug/g, dry basis</u>	<u>BTEX³ ug/g, dry basis</u>
9	85.8	220, 200 ²	ND <0.2 ⁴
12	94.0	58	ND <0.2
13	89.1	44	ND <0.2
G1	91.4	680	ND <0.2
G2	93.0	290	ND <0.2

ND means not detected.

¹ Total petroleum hydrocarbons

² Duplicate determinations. Recovery of 460 ug/g spike added to sample 13: 80%.

³ Benzene, toluene, ethylbenzene, xylene.

⁴ Detection limit: 0.2 ug/g of each compound.



State of New Hampshire
DEPARTMENT OF ENVIRONMENTAL SERVICES

6 Hazen Drive, P.O. Box 95, Concord, NH 03302-0095

603-271-3503 FAX 603-271-2867

TDD Access: Relay NH 1-800-735-2964



September 9, 1993

Mr. Jeffrey O'Hearn
Environmental Project Engineer
James River Corporation
650 Main Street
Berlin, NH 03570-2489

RE: PETROLEUM CONTAMINATED SOILS

Dear Mr. O'Hearn:

The New Hampshire Department of Environmental Services (Department) has received your letter of August 27, 1993 regarding petroleum contaminated soils generated during the removal of underground storage tanks at the Lakeside logging camp in Cambridge and the former James River facility in Groveton. Analytical test data included with your letter shows that the soils contain less than 700 ppm of total petroleum hydrocarbons with no detectable BTEX compounds. It is therefore acceptable to the Department to dispose these soils at the Mt. Carberry landfill.

Please contact me at 271-2925, if you have any questions.

Sincerely,

Carl F. Woodbury
Waste Management Specialist IV
Solid Waste Compliance Section
Waste Management Division

RSR/CFW/neo/6450j

cc: Dr. Raymond Danforth, JRC
Berlin File/DB
Carl F. Woodbury, SWCS

AIR RESOURCES DIV.
64 No. Main Street
Caller Box 2033
Concord, N.H. 03302-2033
Tel. 603-271-1370
Fax 603-271-1381

WASTE MANAGEMENT DIV.
6 Hazen Drive
Concord, N.H. 03301
Tel. 603-271-2900
Fax 603-271-2456

WATER RESOURCES DIV.
64 No. Main Street
P.O. Box 2008
Concord, N.H. 03302-2008
Tel. 603-271-3406
Fax 603-271-1381


WATER SUPPLY & POLLUTION CONTROL DIV.
P.O. Box 95
Concord, N.H. 03302-0095
Tel. 603-271-3503
Fax 603-271-2181

State of New Hampshire
DEPARTMENT OF ENVIRONMENTAL SERVICES

6 Hazen Drive, P.O. Box 95, Concord, NH 03302-0095

603-271-3503 FAX 603-271-2867

TDD Access: Relay NH 1-800-735-2964



March 1994

TO: UST Facility Owners, Carroll, Coos and Grafton Counties

RE: RSA 146-C:4, Underground Storage Facility Permit Fees

Dear Sir/Madam:

On February 20, 1990, the legislature enacted an amendment to RSA 146-C:4 which established a permit fee for underground storage facilities.

Under the legislation, a permit fee of \$70 per year shall be paid to the New Hampshire Department of Environmental Services (NHDES) by the owner or operator of each permitted facility, except for facilities owned by the state and local governments, including counties, and school districts, in the manner described below.


Facilities with existing permits in Carroll, Coos or Grafton counties will expire on April 30, 1994. A total of \$350.00 is due on April 30, 1994. This fee covers the operation permit for the next 5 years, i.e. 1994-1999.

Upon payment of the amount due, your Permit to Operate will be issued.

Please note that no facility shall operate without a valid operation permit.

An invoice and return envelope is included with this letter for your convenience. If you have any questions please contact our office at (603) 271-3644.

Sincerely,


Lynn A. Woodard
Groundwater Protection Bureau

TRB/emw:8191
cc: File

RESOURCES DIV.
64 No. Main Street
Cutter Box 2033
Concord, N.H. 03302-2033
Tel. 603-271-1370
Fax 603-271-1381

WASTE MANAGEMENT DIV.
6 Hazen Drive
Concord, N.H. 03301
Tel. 603-271-2900
Fax 603-271-2456

WATER RESOURCES DIV.
64 No. Main Street
P.O. Box 2008
Concord, N.H. 03302-2008
Tel. 603-271-3406
Fax 603-271-6588

WATER SUPPLY & POLLUTION CONTROL DIV.
P.O. Box 95
Concord, N.H. 03302-0095
Tel. 603-271-3503
Fax 603-271-2181

667142T

FORM NO. 484-B REV. 5/92

JAMES RIVER CORPORATION
Berlin, New Hampshire

02245644

Remittance Advice

Invoice Date	Vendor Invoice No./Our Reference	Invoice Amount	Discount	Net Amount
04 11 94	9474 148566	350.00	.	350.00
		350.00	0.00	350.00



JAMES RIVER CORPORATION

P.O. Box 2218, Richmond, VA 23217

BERLIN/GORHAM DISBURSEMENT

Citibank Delaware
A subsidiary of Citicorp
One Penn's Way
New Castle, DE 1972002245644 -
003718362-20
311

000004589

Date

Amount

Pay
To The
Order
Of

TREASURER STATE OF NH WATER
NHDES
PO BOX 95 6 HAZEN DRIVE
CONCORD NH
03302-0095

04 11 94

*****350.00

Pat A. Nelson
J. M. Nelson

NOT VALID AFTER 60 DAYS

⑈02245644⑈

⑈031100209⑈

38841841⑈

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Tractor Shop
650 Main St. Berlin, NH 03570

Tank#: 14
Tank Volume: 3000 gallons
Contents: Unleaded Gasoline
Removal Date: August 16, 1994

Visual Inspection:

No groundwater was present in the pit when the tank was removed. There was some minimal soil contamination evident in the area at the south end of the tank between this tank and a 3000 gallon diesel tank (Tank #15). The tank was in excellent condition and no holes were detected. The piping and fittings also seemed to be free of leaks.

Olfactory Inspection:

VOC headspace analysis HNU PI101 10.2 eV PID

North end of tank (2A)	4.4 ppm
West side of tank (2C)	2.4 ppm
South end of tank (2B)	76 ppm

Removal Actions:

Three grab samples of soil were taken from the walls of the pit at approximately 4 feet deep in locations at each end of the tank and one on the west side. The soil at the south end of the tank is stockpiled awaiting disposal at our Mt. Carberry Landfill following review of analytical results.

Laboratory Results:

Sample	2A	2B	2C
% Solids	90	91	88
TPH (dry basis)	ND<10	ND<10	ND<10
BTEX	(see attached analytical results)		
MTBE	ND<0.1	ND<0.1	ND<0.1

Disposal:

The pit was filled in with fill following the removal of the tank and lines. The tank was inspected to ensure cleanliness and shipped to Isaacson Structural Steel for disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines June 1994

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Tractor Shop
650 Main St. Berlin, NH 03570

Tank#: 15
Tank Volume: 3000 gallons
Contents: Diesel Fuel
Removal Date: August 16, 1994

Visual Inspection:

No groundwater was present in the pit when the tank was removed. There was some minimal soil contamination evident in the area at the north end of the tank between this tank and a 3000 gallon gasoline tank (Tank #14). The tank was in excellent condition and no holes were detected. The piping and fittings also seemed to be free of leaks.

Olfactory Inspection:

VOC headspace analysis HNU PI101 10.2 eV PID

South end of tank (1A)	2.0 ppm
West side of tank (1C)	42 ppm
North end of tank (2B)	76 ppm

Removal Actions:

Three grab samples of soil were taken from the walls of the pit at approximately 4 feet deep in locations at each end of the tank and one on the west side. The soil at the north end of the tank and west side of tank are stockpiled awaiting disposal at our Mt. Carberry Landfill following review of analytical results.

Laboratory Results:

Sample	1A	1C	2B
% Solids	91	88	91
TPH (dry basis)	ND<10	1100	ND<10
BTEX	(see attached analytical results)		

Disposal:

The pit was filled in with fill following the removal of the tank and lines. The tank was inspected to ensure cleanliness and shipped to Isaacson Structural Steel for disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines June 1994

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.

UNDERGROUND STORAGE TANK REMOVAL

Facility: James River Corporation
Address: Sawmill Hydro
650 Main St. Berlin, NH 03570

Tank#: 11
Tank Volume: 2000 gallons
Contents: Kerosene Heating Oil
Removal Date: August 16, 1994

Visual Inspection:

No groundwater was present in the pit when the tank was removed. The tank was in excellent condition and no holes were detected. The piping and fittings also seemed to be free of leaks.

Olfactory Inspection:

VOC headspace analysis HNU PI101 10.2 eV PID

North end of tank	5.8 ppm
West side of tank	5.8 ppm
South end of tank	5.8 ppm

Removal Actions:

Four grab samples of soil were taken from the walls of the pit at approximately 4 feet deep in locations around the tank perimeter and were composited into one sample. No high spots were detected with the VOC analyzer.

Laboratory Results:

Sample	11
% Solids	93
TPH (dry basis)	ND<100
BTEX	(see attached analytical results)

Disposal:

The pit was filled in with fill following the removal of the tanks and lines. The tank was inspected to ensure cleanliness and shipped to Isaacson Structural Steel for disposal as scrap metal.

Procedure based on:

UST Closure, Sampling and Reporting Guidelines June 1994

Interim Policy for Management of Soils Contaminated from
Spills/Releases of Virgin Petroleum Products 9/91 and
Amendment of 3/24/92.

State of New Hampshire regulations Part Env-Ws 411.